		****				
FORM (REV	PTO-139 10-95)	0 U.S DEPARTMENT OF	COMMERCE PATENT AND TRADEMARK OFFI	CE ATTORNEYS DOCKET NO.		
	,	TD ANGMITTAL LETTED TO T	THE INTERNATED	3699-2-PUS		
TRANSMITTAL LETTER TO THE UNITED STATI DESIGNATED/ELECTED OFFICE (DO/EO/US)				U.S. APPLICATION NO. (If known, see 35 CFR 1.5)		
CONCERNING A FILING UNDER				09/646141		
INTE	RNATIO	NAL APPLICATION NO.	INTERNATIONAL FILING DATE	PRIORITY DATE CLAIMED		
		PCT/US97/08842	05 June 1997	14 March 1997		
TITLE	TITLE OF INVENTION "COPY PROTECTABLE OPTICAL MEDIA DEVICE AND METHODOLOGY THEREFOR"					
APPLICANT(S) FOR DO/EO/US						
McLAUGHLIN et al.						
Applicant herewith submits to the United States Designated/Elected Office (DO/EO/US) the following items and other information:						
1.	[X]	This is a FIRST submission of items concerning a filing under 35 U.S.C. 371.				
2.	[]	This is a SECOND or SUBSEQUENT submission of items concerning a filing under 35 U.S.C. 371.				
3.	[X]	This express request to begin national examination procedures (35 U.S.C. 371(f))) at any time rather than delay examination until the expiration of the applicable time limit set in 35 U.S.C. 371(b) and PCT Articles 22 and 39(l).				
4.	[X]	A proper Demand for International Preliminary Examination was made by the 19th month from the earliest claimed priority date.				
5.	[X]	A copy of the International Application as filed (35 U.S.C. 371(c)(2))				
		a. [ ] is transmitted herewith (rec	uired only if not transmitted by the Intern	national Bureau).		
		b. has been transmitted by the International Bureau				
		c. [X] is not required, as the application was filed in the United States Receiving Office (RO/US).				
6.	[]	A translation of the International Application into English (35 U.S.C. 371(c)(2)).				
7.	[X]	Amendments to the claims of the International Application under PCT Article 19 (35 U.S.C. 371(c)(3)).				
		a. [ ] are transmitted herewith (required only if not transmitted by the International Bureau).				
		b. [ ] have been transmitted by the	e International Bureau.	·		
ļ.		c. have not been made; however, the time limit for making such amendments has NOT expired.				
Ī		d. [X] have not been made and wi	ll not be made.			
<b>≛</b> 8.	[]	A translation of the amendments to the claims under PCT Article 19 (35 U.S.C. 371(c)(3)).				
<u> </u>	[X]	An oath or declaration of the inventor(s) (35 U.S.C. 371(c)(4)).				
10.	[]	A translation of the annexes to the International Preliminary Examination Report under PCT Article 36 (35 U.S.C. 371(c)(5)).				
Items 11. To 16. below concern documents or information included:						
11.	[]	An Information Disclosure Statement under 37n CFR 1.97 and 1.98.				
12.	[X]	An assignment document for recording. A separate cover sheet in compliance with 37 CFR 3.23 and 3.31 is included.				
13.	[]	A FIRST preliminary amendment.				
14.	[]	A SECOND or SUBSEQUENT preliminary amendment.				
15.	[]	A substitute specification.				
16.	[]	A change of power of attorney and/or address letter.				
17.	[X]	Other items or information:				
		Petition to Correct an Obvious Error and	to DATE OF DEPOSIT: Se	ING LABEL NUMBER: EL417658322 eptember 13, 2000		
		Revive an Unintentionally Abandoned A	THEREBY CERTIFY TH THE UNITED STATES I ADDRESSEE" SERVIC ABOVE AND IS ADDR	AT THIS PAPER OR FEE IS BEING DEPOSITED WITH POSTAL SERVICE "EXPRESS MAIL POST OFFICE TO E UNDER 37 CFR 1.10 ON THE DATE INDICATED ESSED TO THE ASSISTANT COMMISSIONER FOR VASHINGTON, D.C. 20231.		
			TYPED OR PRINTED N			
			SIGNATURE:	110 Money		

# 430 Rec'd PCT/PTO 1 3 SEP 2000

BASIC NATIONAL FEE (37 CFR 1.492(a)(1)-(5)):   Search Report has been prepared by the EPO or IPO   \$840.00     International preliminary examination fee paid to USPTO (37 CFR 1.482)   \$670.00     No international preliminary examination fee paid to USPTO (37 CFR 1.482)   \$670.00     Neither international preliminary examination fee (37 CFR 1.482) nor international search fee for 37 CFR 1.445(a)(2))   \$760.00     Neither international preliminary examination fee paid to USPTO (37 CFR 1.482) and all claims satisfied provisions of PCT Article 33(2)-(4)   \$96.00     ENTER APPROPRIATE BASIC FEE AMOUNT   \$96.00     Surcharge of \$130.00 for furnishing the oath or declaration later than   20	ER						
Search Report has been prepared by the EPO or JPO   \$840.00   International preliminary examination fee paid to USPTO (37 CFR 1.482)   \$670.00   No international search fee paid to USPTO (37 CFR 1.482)   \$760.00   Neither international search fee paid to USPTO (37 CFR 1.482)   \$760.00   Neither international preliminary examination fee 03 CFR 1.482   or international search fee (37 CFR 1.445(a)(2)) paid USPTO   \$970.00   International preliminary examination fee 03 CFR 1.482   or international preliminary examination fee 03 CFR 1.482   or international preliminary examination fee 03 CFR 1.482   or international preliminary examination fee paid to USPTO (37 CFR 1.482)   \$96.00     ENTER APPROPRIATE BASIC FEE AMOUNT   \$96.00     Surcharge of \$130.00 for furnishing the oath or declaration later than   20	JSE ONLY						
International preliminary examination fee paid to USPTO (37 CFR 1.482)  No international preliminary examination fee paid to USPTO (37 CFR 1.482) but international preliminary examination fee paid to USPTO (37 CFR 1.482) but international search fee paid to USPTO (37 CFR 1.482) No international preliminary examination fee (37 CFR 1.482) nor international search fee (37 CFR 1.48(a)(2)) paid USPTO \$970.00  International preliminary examination fee (37 CFR 1.482) nor international preliminary examination fee paid to USPTO (37 CFR 1.482) and all claims satisfied provisions of PCT Article 33(2)-(4) \$96.00  Surcharge of \$130.00 for furnishing the oath or declaration later than [] 20 [X] 30 \$130.00  Surcharge of \$130.00 for furnishing the oath or declaration later than months from the earliest claimed priority date (37 CFR 1.492(e)).  CLAIMS NUMBER FILED NUMBER EXTRA RATE  Total Claims 42 -20 = 22 x \$18.00 \$396.00  MULTIPLE DEPENDENT CLAIMS(S) (if applicable) + \$260.00 \$1,404.00  MULTIPLE DEPENDENT CLAIMS(S) (if applicable) + \$260.00 \$2,006.00  Preduction of ½ for filing by small entity, if applicable. Verified Small Entity Statement must also be filed Solve of \$130.00 for furnishing the English translation later than [] 20 [] 30 \$30.0							
No international preliminary examination fee paid to USPTO (37 CFR 1.482)							
No international preliminary examination fee paid to USPTO (37 CFR 1.482) but international search fee paid to USPTO (37 CFR 1.4482) nor international search fee paid to USPTO (37 CFR 1.4482) nor international search fee (37 CFR 1.445(a)(2)) paid USPTO							
but international search fee paid to USPTO (37 CFR 1.445(a)(2)) \$760.00  Neither international preliminary examination fee (37 CFR 1.482) nor international search fee (37 CFR 1.43(a)(2)) paid USPTO \$970.00  International preliminary examination fee paid to USPTO (37 CFR 1.482) and all claims satisfied provisions of PCT Article 33(2)-(4) \$96.00  ENTER APPROPRIATE BASIC FEE AMOUNT = \$96.00  Surcharge of \$130.00 for furnishing the oath or declaration later than months from the earliest claimed priority date (37 CFR 1.492(e)).  CLAIMS NUMBER FILED NUMBER EXTRA RATE  Total Claims 42 - 20 = 22 x \$18.00 \$396.00 \$1,404.00  Independent Claims 21 - 3 = 18 x578.00 \$1,404.00 \$1,404.00  MULTIPLE DEPENDENT CLAIMS(S) (if applicable) + \$260.00 \$2,406.00 \$4,406							
international search fee (37 CFR 1.445(a)(2)) paid USPTO							
### Substitute of \$130.00 for furnishing the oath or declaration later than months from the earliest claimed priority date (37 CFR 1.492(e)).    Surcharge of \$130.00 for furnishing the oath or declaration later than months from the earliest claimed priority date (37 CFR 1.492(e)).    CLAIMS   NUMBER FILED   NUMBER EXTRA   RATE							
Surcharge of \$130.00 for furnishing the oath or declaration later than months from the earliest claimed priority date (37 CFR 1.492(e)).  CLAIMS NUMBER FILED NUMBER EXTRA RATE  Total Claims 42 - 20 = 22 x \$18.00 \$ 396.00   Independent Claims 21 - 3 = 18 x \$78.00 \$ 1,404.00    MULTIPLE DEPENDENT CLAIMS(S) (if applicable) +\$260.00 \$ \$ 1,404.00    Reduction of ½ for filing by small entity, if applicable. Verified Small Entity Statement must also be filed (Note 37) (FFR 1.9, 1.27, 1.28).  Reduction of ½ for filing by small entity, if applicable. Verified Small Entity Statement must also be filed (Note 37) (FFR 1.9, 1.27, 1.28).  SUBTOTAL = \$ SUBTOTAL = \$ \$ SUB							
months from the earliest claimed priority date (37 CFR 1.492(e)).  CLAIMS NUMBER FILED NUMBER EXTRA RATE  Total Claims 42 - 20 = 22 x \$18.00 \$ 396.00 \$ 1,404.00 \$ 1,							
CLAIMS NUMBER FILED NUMBER EXTRA RATE  Total Claims							
Independent Claims 21 - 3 = 18 x \$78.00 \$ 1,404.00    MULTIPLE DEPENDENT CLAIMS(S) (if applicable) + \$260.00 \$    Reduction of ½ for filing by small entity, if applicable. Verified Small Entity Statement must also be filed [Note 37i CFR 1.9, 1.27, 1.28).  SUBTOTAL S SUBTOTAL = S    Processing fee of \$130.00 for furnishing the English translation later than   20   30    months from the earliest claimed priority date (37 CFR 1.492(f)). +    TOTAL NATIONAL FEE = S    Fee for recording the enclosed assignment (37 CFR 1.21(h)). The assignment must be accompanied by an appropriate cover sheet (37 CFR 3.28, 3.31) \$40.00 per property    TOTAL FEES ENCLOSED =   \$2,066.00    Amount to be: refunded    charged   \$  X A check in the amount of \$2,066.00    Description of ½ to cover the above fees is enclosed.  Description of ½ to cover the above fees. A duplication of this sheet is enclosed.							
MULTIPLE DEPENDENT CLAIMS(S) (if applicable) +\$260.00 \$  TOTAL OF ABOVE CALCULATIONS = \$2,026.00 \$  Reduction of ½ for filing by small entity, if applicable. Verified Small Entity Statement must also be filed \$  (Note 37i CFR 1.9, 1.27, 1.28).  SUBTOTAL = \$  Processing fee of \$130.00 for furnishing the English translation later than []20 []30 \$  months from the earliest claimed priority date (37 CFR 1.492(f)). +  TOTAL NATIONAL FEE = \$  Pree for recording the enclosed assignment (37 CFR 1.21(h)). The assignment must be accompanied by an appropriate cover sheet (37 CFR 3.28, 3.31) \$40.00 per property +  TOTAL FEES ENCLOSED = \$2,066.00 Amount to be: refunded charged \$  a. [X] A check in the amount of \$2,066.00 to cover the above fees is enclosed.  b. [] Please charge my Deposit Account No in the amount of \$ to cover the above fees. A duplication of this sheet is enclosed.							
TOTAL OF ABOVE CALCULATIONS = \$ 2,026.00  Reduction of ½ for filing by small entity, if applicable. Verified Small Entity Statement must also be filed \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$							
Reduction of ½ for filing by small entity, if applicable. Verified Small Entity Statement must also be filed [Note 37i CFR 1.9, 1.27, 1.28).  SUBTOTAL = \$  Processing fee of \$130.00 for furnishing the English translation later than []20 []30							
SUBTOTAL =   S   SUBTOTAL =   S   Processing fee of \$130.00 for furnishing the English translation later than   [ ] 20							
Processing fee of \$130.00 for furnishing the English translation later than months from the earliest claimed priority date (37 CFR 1.492(f)).  TOTAL NATIONAL FEE = \$  Fee for recording the enclosed assignment (37 CFR 1.21(h)). The assignment must be accompanied by an appropriate cover sheet (37 CFR 3.28, 3.31) \$40.00 per property + TOTAL FEES ENCLOSED = \$2,066.00  Amount to be: refunded charged \$  a. [X] A check in the amount of \$2,066.00 to cover the above fees is enclosed.  b. [] Please charge my Deposit Account No in the amount of \$ to cover the above fees. A duplication of this sheet is enclosed.							
TOTAL NATIONAL FEE = \$  Fee for recording the enclosed assignment (37 CFR 1.21(h)). The assignment must be accompanied by an appropriate cover sheet (37 CFR 3.28, 3.31) \$40.00 per property +   TOTAL FEES ENCLOSED = \$ 2,066.00  Amount to be: refunded charged \$  a. [X] A check in the amount of \$2,066.00 to cover the above fees is enclosed.							
Fee for recording the enclosed assignment (37 CFR 1.21(h)). The assignment must be accompanied by an appropriate cover sheet (37 CFR 3.28, 3.31) \$40.00 per property + TOTAL FEES ENCLOSED = \$2,066.00  Amount to be: refunded charged \$  a. [X] A check in the amount of \$2,066.00 to cover the above fees is enclosed.  b. [] Please charge my Deposit Account No in the amount of \$ to cover the above fees. A duplication of this sheet is enclosed.							
TOTAL FEES ENCLOSED = \$ 2,066.00  Amount to be: refunded charged \$  a. [X] A check in the amount of \$ 2,066.00 to cover the above fees is enclosed.  b. [] Please charge my Deposit Account No in the amount of \$ to cover the above fees. A duplication of this sheet is enclosed.							
TOTAL FEES ENCLOSED = \$ 2,066.00  Amount to be: refunded charged \$  a. [X] A check in the amount of \$ 2,066.00 to cover the above fees is enclosed.  b. [] Please charge my Deposit Account No in the amount of \$ to cover the above fees. A duplication of this sheet is enclosed.							
a. [X] A check in the amount of \$2,066.00 to cover the above fees is enclosed.  b. [] Please charge my Deposit Account No in the amount of \$ to cover the above fees. A duplication of this sheet is enclosed.							
a. [X] A check in the amount of \$2,066.00 to cover the above fees is enclosed.  b. [] Please charge my Deposit Account No in the amount of \$ to cover the above fees. A duplication of this sheet is enclosed.							
a. [X] A check in the amount of \$2,066.00 to cover the above fees is enclosed.  b. [ ] Please charge my Deposit Account No in the amount of \$ to cover the above fees. A duplicate of this sheet is enclosed.							
b. [ ] Please charge my Deposit Account No in the amount of \$ to cover the above fees. A duplica of this sheet is enclosed.							
of this sheet is enclosed.	a. [X] A check in the amount of $$2,066.00$ to cover the above fees is enclosed.						
C. [X] The Commissioner is hereby authorized to shares any additional face which were be required.							
c. [X] The Commissioner is hereby authorized to charge any additional fees which may be required, or credit any overpayment to Deposit Account No. 19-1970. A duplicate copy of this sheet is enclosed.							
NOTE: Where an appropriate time limit under 37 cfr 1.494 or 1.495 has not been met, a petition to revive (37 cfr 1.137(a) or (b)) must be filed and granted to restore the application pending status.							
SEND ALL CORRESPONDENCE TO:							
SHERIDAN ROSS P.C.  1560 Broadway, Suite 1200  Denver, Colorado 80202-5141  Telephone: (303) 863-9700  Facsimile: (303) 863-0223  Joseph E. Kovarik  Registration No. 33,005							

25

09/646/4/ 03 Recd PCT/FTO 13 SEP 2000

## COPY PROTECTABLE OPTICAL MEDIA DEVICE AND METHODOLOGY THEREFOR

#### FIELD OF INVENTION

The present invention broadly relates to data storage media for use with optical scanning machines, which data storage media are adapted to limit access to information stored thereon. More particularly, the present invention concerns optical disks for use in an optical readout system of a computer to limit continual or repeated unrestricted access to stored data by the optical readout system. A method is also provided for limiting access to data stored in an optical medium environment.

#### 15 BACKGROUND OF THE INVENTION

The computer industry has long been plagued by the illegal misappropriation of software products. Software Publisher's Association (SPA), an organization with devotes significant resources to tracking analyzing piracy problems, has determined that in 1994 alone the personal computer software industry lost in excess of \$8 billion due to illegal copying of business application software. The SPA further estimated that virtually half of the business software in use in 1994 was pirated, and this estimate does not include the illegal copying of operating systems, education, entertainment or personal productivity software. The piracy problem is particularly acute in more developed markets such as the United States.

Many approaches have been implemented by software producers in an effort to combat piracy. Some of these approaches include encryption, special data formatting complex installation procedures, and passwords, to name only a few. Unfortunately, end user resistance to these anti-piracy schemes has been high because they are plaqued

15

20

25

30

35

by one or more limitations, such as an inability to "try before you buy", restrictions on the generation of legitimate back-up copies, and password protection techniques which fail once the password is divulged or discovered. The inability of copy protection schemes to win end-user acceptance has been so extreme that many publishers have simply abandoned the effort, choosing instead to rely on the integrity of their customers to abide by copyright laws.

The of misappropriation software is rampant irrespective of whether the data storage medium is magnetic Magnetic storage disks are particularly or optical. susceptible to piracy. Commercially available magnetic the conventional floppy disk, disks, such as read/write/erase memory devices in which data is stored in a magnetizable surface layer as discrete patterns of magnetism. Information is stored and retrieved by a read/write head which contains a coil wound around an iron core.

While the magnetic recording medium remains the most popular, there has been a growing trend in recent years to utilize an optical medium environment for the storage and retrieval of data. The reason for this trend is readily apparent. A commercially available magnetic floppy disk is only capable of storing 1.44Mb of data, whereas an optical CD-ROM of the same size can have a capacity in excess of 600Mb.

In a typical optical disk for use in a computer's optical readout system, data is stored as a series of lands and pits. This is accomplished by stamping along spiral tracks on a transparent plastic disk, overlaying this with a reflective coating, and thereafter superimposing a protective layer over this coating. Light from a semiconductor laser is focused onto either the lands or pits from below and the reflected light impinges upon a

20

25

30

photodetector which converts the presence or absence of the pits into a binary electrical signal. Because the focused laser spot is so minute, the amount of information that can be stored onto the surface of the disk is immense.

- Adjacent tracks need only be spaced apart by approximately .6µm and, hence, 20,000 tracks may be available on a conventional 120 mm diameter (5 inch) optical disk. The electrical signals delivered to the optical readout system correspond to the magnitude of the
- reflected light which either increases or decreases due to interference and/or diffraction by the preformatted data structures.

In the 1970's, researchers began attempting to encode information on optical disks with lasers, and the video disk was subsequently developed. In the 1980's, more sensitive materials that could be encoded with a low power diode laser were developed. These diode lasers, operating at a wavelength of approximately 800 nm, are now universally employed to read audio and computer CD's. Following the advent of compact disks which are capable of being read with a laser diode, researchers have now endeavored to develop a marketable compact disk upon which data can be recorded by an end user. The benefit of this capability, as discussed above, is that optical laser recording provides a much higher information density than magnetic recording.

Presently, there is a write once and read many times (WORM) compact disk. This compact disk utilizes a dye that irreversibly changes state when exposed to a high power laser diode and maintains this state when read with a low power reading laser. As such, detection of the encoded data by the optical readout system does not affect the encoded data.

It is anticipated that the next generation of optical disks will be capable of being written on, read, erased and

10

15

20

25

30

35

rewritten on, etc. many times, similar to a magnetic disk. A photochromic material, or chromophore, is attractive for this purpose. Photochromism is the phenomenon whereby the absorption spectrum of a molecule or crystal changes reversibly when the material is irradiated by light possessing certain wavelengths. Thus, for example, a colorless compound may change its molecular state to a quasi-stable colored state when radiated by ultraviolet (UV) light, yet be returned to the colorless state upon exposure to visible light. Both organic and inorganic materials which exhibit these properties have been known for years.

Recently, photochromic compounds have attracted much attention in the field of optical recording. As discussed in Jun'Etsu Seto, Photochromic Dves, the photochromic materials initially studied for such an application did not have significant sensitivity in the infrared region near 800 nm, the wavelength region of conventional laser diodes. Seto recognizes, however, that a specific class photochromic compounds, known as spiropyrans, can be manipulated to exhibit improved sensitivity in the infrared Specifically, Seto discusses a class of region. photochromic spiropyrans with benzothiopyran units in the molecular framework and concludes that the synthesized spirobenzothiopyran is well suited to the requirements of erasable optical recording media for systems conventional laser diodes.

Another dye of the spiropyran class, having the chemical composition 6-nitro-1'3'3'-trimethylspiro[2H-1-benzothiopyran-2,2'-indoline], or 6-nitro-1-SBIPS for short, is discussed in Tarkka, Richard U., Talbot, Marc E., et al., "Holographic Storage in a near-ir sensitive photochromic dye", Optic Comm. 109, 54-58 (1994). This article discusses the use of 6-nitro-1-S-BIPS for use in the holography field wherein the dye becomes colored when

10

15

20

25

30

35

exposed to light having a wavelength of 780 nm. The film returns to a quasiclear state upon exposure to an ultraviolet light source at 337 nm.

It is anticipated, based on these recent developments, that the conventional magnetic disk will eventually become obsolete due to the recent developments in optical storage technology. Concurrent with this anticipated phaseout of magnetic disks will be a need to adequately address the piracy issues which have for so long plagued the software that the illegal misappropriation industry 50 proprietary rights can be thwarted. Accordingly, while past research has concentrated on utilizing photochromic materials for the recording of information on compact disks, the present inventors have realized that similar photochromic materials may also be used to protect the compact disk against illegal copying and distribution. addition, the present inventors have also recognized that certain other photoreactive materials, as well as oxygen reactive materials, may be employed for this purpose. is, compounds such as these may be used to deny access to a specially coated compact disk beyond one or more authorized uses. That is, such compounds, when applied as a coating on a disk, operate to effectively change its light transmissive properties upon exposure to a low power reading laser, thereby darkening the coating on the disk and rendering data undetectable by an optical readout system. Moreover, the inventors have also recognized other optical media data protection techniques for the present invention that also address the unrestricted duplication of information as discussed hereinabove.

#### SUMMARY OF INVENTION

It is an object of the present invention to provide a new and useful optical medium, such as an optical disk, and system therefor which is adapted for use with an optical

10

15

20

25

30

35

readout system of, for example, a computer, wherein the readout system includes a light source operative to produce an interrogating beam of light for reading data structures on the optical medium.

Another object of the present invention is to provide such an optical medium which is particularly adapted to prevent unrestricted access to encoded information thereon by an optical readout system, wherein the information may be, for example, graphical data, video data, audio data, text data, and/or a software program.

Another object of the present invention is to use the error detection capabilities of a conventional optical medium reader for: (a) determining a status of an optical medium provided by the present invention, and/or (b) verifying an object or person as authentic. That is, it is an object of the present invention to use the errors detected on the optical medium for (a) and/or (b) above. For example, the total number of errors detected in a predetermined area of the optical medium, the density of the errors detected in a predetermined location of the optical medium, and/or the pattern of errors in a predetermined area of the optical medium provides, according to the present invention, sufficient information for (a) and/or (b) above.

Another object of the present invention is to provide verification or authentication of information provided on or with the novel optical medium of the present invention. For example, the present invention may be used for verifying the authenticity of an optical disk having an audio and/or multimedia presentation thereon. Additionally, when the optical medium of the present invention is incorporated into, for example, a financial transaction card, the card can be verified as authentic.

Another object of the present invention is to provide verification or authentication of a user that is, for

10

15

20

25

30

35

example, desirous of making an electronic financial transaction such as on the Internet.

A further object of the present invention is to provide a new and useful optical disk which is relatively easy to manufacture without substantial increases in costs.

Yet another object of the present invention is to provide a methodology of limiting access to information stored on an optical medium for use in a computer's optical readout system.

Still a further object of at least some embodiments of the present invention is to provide an optical disk which is particularly constructed so that an end user is unaware of the disk copy protection features until after they have been performed.

A first collection of embodiments of the present invention accomplishes these objectives by providing an article of manufacture (e.g., an optical disk) that is adapted to be encoded with data and further adapted so that duplication of the data by an optical scanning machine (i.e., an optical readout system) may be restricted. article of manufacture comprises a substrate fabricated from a selected material, with a surface thereof provided with the data. A reactive compound is formed as a coating on at least a portion of the substrate surface and the reactive compound operates to change from an optically transparent state to an optically opaque state in response to irradiation for an accumulated duration of time by infrared light having desired characteristics, thereby to prevent light from the optical scanning machine from penetrating the reactive compound and to render the data undetectable by the optical scanning machine.

More particularly, an optical disk is provided which is adapted for use in an optical readout system of a computer wherein the optical readout system includes a light source operative to produce an interrogating beam of

15

20

25

30

35

light for reading data structures. Broadly, the optical disk according to the first collection of embodiments of the present invention includes an inner layer having an upper surface and a lower surface, with the lower surface thereof encoded with information stored as a plurality of data structures that are readable by the interrogating beam of light. The outer layer is disposed in a confronting relationship with the lower surface, and a film of a reactive compound is superimposed over at least some of these data structures. The reactive compound is selected to be of a type which is operative to change physical characteristics in response to a selected stimulus, thereby to affect readability of the data by the interrogating beam.

Preferably, the optical disk includes a layer of reflective material interposed between the lower surface and the reactive compound. This reactive compound may be supported on a lower surface of the disk's second layer and have a thickness of approximately 2-5 microns or, alternatively, it may be interposed between the lower surface and the disks outer layer. The lower surface is preferably contoured to include a sequence of pits and lands which define the plurality of data structures, with the reactive compound superimposed over at least some of these pits and lands.

The selected stimulus to which the reactive compound responds is an ambient environment selected to be either visible light, infrared light, light and oxygen, or simply air. Where the stimulus is light alone, the reactive compound may be a photoreactive material and preferably one selected from a spiropyran class of photochromic compounds. One such compound may be 6-nitro-1'3'3'-trimethylspiro-[2H-1benzothiopyran-2,2'-indoline], or 6-nitro-1-S-BIPS for short. Such a photochromic compound is operative to change from an optically opaque or darkened condition in response

10

15

20

25

30

35

to an interrogating beam wavelength of approximately 780 nanometers (nm) and thereafter return to an optically transparent condition in response to a irradiation by a beam of light having a wavelength of approximately 337 nanometers (nm).

Where the stimulus is a combination of light and oxygen, the reactive compound would therefore be photoreactive with oxygen and preferably operate to change its physical characteristics in response to an interrogating beam of light having a wavelength of approximately 650 nanometers (nm), which is encountered with digital versatile disk (DVD) readers.

Where the environmental stimulus is simply air (more precisely, oxygen), the reactive compound may be one which is operative after an accumulated duration of time to oxidize and alter an optical characteristic thereof. For example, such a reactive compound would change from an optically transparent condition to an optically opaque condition wherein it absorbs light having a wavelength within a desired range. This wavelength could be either 650 nanometers (nm), as discussed above, but may also be in the range of 780 to 820 nanometers (nm). The oxidizing reactive compound may be selected from a group of dyes consisting of methylene blue, brilliant cresyl blue, basic blue 3 and toluidine blue 0.

A methodology of limiting access to data stored on an optical medium such as an optical disk is provided by the first collection of embodiments. Broadly, this methodology comprises the steps of rotating an optical disk in a disk drive at a selected rotational speed, with the optical disk including a substrate layer encoded with information stored thereon as a plurality of readable data structures. A reactive compound is preferably superimposed over at least some of these data structures and this reactive compound operates in an ambient environment containing oxygen to

10

15

20

25

30

35

change optical transmission in response to irradiation for an accumulated duration of time by light having a beam wavelength that is within a selected range. An interrogating beam of light having a beam wavelength that is within the selected range is directed toward the substrate layer and through the reactive compound for the accumulated duration of time.

The step of directing the interrogating beam may be accomplished by directing the beam at the substrate layer for a continuous interval of time that is sufficient to cause the change in optical transmission through the optical medium. Alteratively, the interrogating beam may be directed at the substrate layer for a plurality of discrete intervals of time sufficient to cause such change. Where this is the case, it is contemplated that the interrogating beam may be selectively advanced radially across an outermost surface of the optical disk until the beam interacts with the reactive compound for the plurality of discrete intervals of time. The interrogating beam's wavelength may be approximately 780 nanometers (nm) where a CD-Rom optical disk is utilized, or have a wavelength of approximately 650 nanometers (nm) which is the wavelength employed for digital versatile disks (DVD). Preferably, interrogating beam also has an intensity the approximately 1 milliwatt (mW) of power, which is typically encountered in conventional optical readers.

In a second collection of embodiments of the present invention, a method and apparatus are provided for prohibiting unrestricted duplication of information on an optical medium such as an optical disk, wherein the user manually affects a physical change to the optical disk during an initial use of the optical disk. For example, the user may activate or perform a predetermined procedure for rendering one or more predetermined areas or locations of the optical disk unreadable or more error prone. This

10

15

20

25

30

35

in effect "marks" the optical disk both visually to the user and computationally to a program for accessing information on the optical disk (e.g., graphical data, video data, audio data, text data and/or a software installation program) as having been previously used for accessing the information on the optical disk. Thus, in a subsequent attempt to access the information on the optical disk (e.g., a subsequent attempt to view a multimedia presentation such as a movie, or a subsequent attempt at reinstallation of a software application on the optical disk), it is possible to detect that the information on the optical disk has been previously accessed due to a change in the information on the disk that is able to be read by an optical reader. For example, the optical reader may detect a greater number of read errors than when the optical disk was first accessed for information retrieval.

Alternatively, in other embodiments of the present invention, instead of purposefully creating unreadable portions of the optical disk, a converse method and apparatus may be employed wherein a predetermined portion initially unreadable optical disk is subsequently becomes readable. That is, a mask or covering may be attached to the optical disk during manufacture so that a predetermined portion of information on the optical disk is initially unreadable by an optical reader, but upon initial use of the optical disk, the user physically removes or changes the mask, thereby allowing a sufficient amount of the previously unreadable portion underneath the mask to be read. Accordingly, optical disk accessing software can be performed that detects a state change in the optical disk due to the removing or changing of the mask.

It is a further aspect of at least some embodiments of the present invention that an encoded identifier is provided to a user upon first use of an optical medium of

10

15

20

25

35

Such an encoded identifier is the present invention. particularly useful for prohibiting unwanted duplication and/or use of commercial software since the identifier is derived from a unique physical change of the optical disk, and, for example, serial numbers of the installation Thus, the encoded identifier, when supplied computer. during a reinstallation attempt and decoded, allows the present invention to determine whether the user attempting to install the software on a computer different from the original installation. Thus, upon detecting a state change indicating the software has been previously installed, the present invention may restrict various kinds of access to the information on the optical medium. particular, if the optical disk provides software programs that may be installed on a user's computer, installations beyond the initial installation may be prohibited if the installation is not on the same computer as the initial installation.

Other collections of embodiments of the present invention are also provided hereinbelow. In particular, collections of embodiments are described relating to verification and/or authentication of financial transaction cards or financial transactions.

These and other objects of the present invention will become more readily appreciated and understood from a consideration of the following detailed description of the exemplary embodiments of the present invention when taken together with the accompanying drawings, in which:

#### BRIEF DESCRIPTION OF DRAWINGS

Fig. 1 is a perspective view of an optical readout system utilizing an optical disk (shown in partial phantom) according to the present invention;

Fig. 2 is a side view in elevation, and in partial cross-section, showing the optical readout system's interrogating beam positioned beneath a first type of data

10

15

20

25

30

35

structure stored on an optical disk according to a first exemplary embodiment of the present invention;

Fig. 3A is an enlarged cross-sectional view of area "A" in Fig. 2;

Fig. 3B is an enlarged cross-sectional view of area "A" in Fig. 2 after an accumulated duration of time so that the reactive compound associated with the optical disk of the first exemplary embodiment of the present invention has undergone a change in its physical characteristics;

Fig. 4 is a side view in elevation, and in partial cross-section, showing the optical readout system's interrogating beam positioned beneath a second type of data structure stored on the optical disk according to the first exemplary embodiment of the present invention;

Fig. 5A is an enlarged cross-sectional view of area "A'" in Fig. 4;

Fig. 5B is an enlarged cross-sectional view of area "A'" in Fig. 4 after an accumulated duration of time so that the reactive compound associated with the optical disk of the first exemplary embodiment of the present invention has undergone a change in its physical characteristics;

Fig. 6A is an enlarged cross-sectional view of an area "Bl" of an optical disk according to a second exemplary embodiment of the present invention, with the optical readout system's interrogating beam positioned beneath a first type of data structure stored thereon;

Fig. 6B is an enlarged cross-sectional view of the same area "B" after an accumulated duration of time so that the reactive compound associated with the optical disk according to the second exemplary embodiment of the present invention has undergone a change in its physical characteristics;

Figure 7A is an enlarged cross-sectional view of an area "B'" of an optical disk according to a second exemplary embodiment of the present invention, with the

10

15

20

25

30

35

optical readout system's interrogating beam positioned beneath a second type of data structure stored thereon;

Fig. 7B is an enlarged cross-sectional view of the same area "B'" after an accumulated duration of time so that the reactive compound associated with the optical disk according to the second exemplary embodiment of the present invention has undergone a change in its physical characteristics;

Fig. 8 is a perspective view, partially pealed away, of a package for containing an optical disk utilizing any one of a variety of reactive compounds according to the present invention; Figure 9 is a bottom plan view showing a variety of applications for the reactive compound associated with an optical disk according to the present invention;

Figs. 10A, 10B and 10C present a flowchart of the steps performed when the present invention is used to install computer software residing on an optical disk that conforms with the inventive aspects of the present invention, wherein the user is required to make a manual change to the optical disk during the first installation using the optical disk;

Figs. 11A and 11B illustrate a manual approach to irreversibly changing the physical characteristics of an optical disk manufactured according to the present invention. That is, the optical disk here includes an additional layer bonded to the optical disk wherein upon removal by the user, the information encoded on the optical adjacent to the additional layer is damaged;

Fig. 12 illustrates the removal of the additional layer (denoted a "ripcord") that is also shown in Figs. 11A and 11B;

Figs. 13A and 13B illustrate an alternative embodiment to the optical disk embodiment of Figs. 11A - 12B for purposefully damaging an optical disk manufactured

10

15

20

25

30

35

according to the present invention. In particular, in Figs. 13A and 13B, a chemical container or sack is bonded to an optical disk so that upon rupturing of the container (during, e.g., an initial optical disk use), the information on the optical disk is purposefully damaged, thereby allowing a subsequent installation process to detect the previous access to the information on the optical disk;

Figs. 14A and 14B illustrates cross-sections of the optical disk of Figs. 13A and 13B, wherein Fig. 14A shows the chemical container prior to rupturing and Fig. 14B shows the chemical container after rupturing;

Figs. 15A and 15B illustrate another alternative embodiment for purposefully damaging an optical disk wherein an external device is used that can etch or scar the optical disk and thereby reduce the readability of disk information in a particular area of the disk;

Figs. 16A and 16B illustrate yet another embodiment of the present invention for purposefully damaging an optical disk manufactured according to the present invention. In the embodiment of these figures, an external device is used for applying one or more chemicals to a particular or predetermined portion of the optical disk and thereby inducing additional read errors from an optical disk reader;

Figs. 17A and 17B illustrate an alternative embodiment of an optical disk manufactured according to the present invention, wherein an additional layer is provided on the optical disk during manufacture for hiding or masking a particular portion of the information on the optical disk;

Fig. 18 illustrates the removal of the additional layer (also denoted a "ripcord") from the optical disk of Figs. 17, wherein the optical disk information masked by the ripcord is now capable of being read by an optical reader;

15

20

25

30

35

Figs. 19A and 19B illustrate another embodiment of the present invention, wherein a container or sack having one or more chemicals is attached to an optical disk during manufacture so that this container initially masks or distorts information encoded into the optical disk; however, upon rupturing of the container, the masked information on the optical disk is now capable of being read by an optical reader;

Fig. 20 illustrates the embodiment of the present invention shown in Figs. 19A and 19B, wherein Fig. 20 shows the cross-section of the optical disk after the chemical container is ruptured; and

Figs. 21A and 21B illustrate the use of an external device having an enclosed chemical that can be used for removing or changing the optical characteristics of a patch or additional layer that masks information on the optical disk;

Fig. 22 is a flowchart of the steps performed in the present invention in verifying the identity of user requesting to perform an electronic financial transaction via, for example, the Internet.

#### DETAILED DESCRIPTION

The present invention is, in one sense directed to an optical disk for use in a computer's optical readout system, which optical disk is constructed to prohibit unrestricted access, by the readout system, to information stored on the disk. As such, the optical disk of the present invention is particularly adapted as an alternative approach for combating the growing piracy problems resulting from the illegal misappropriation of software products. As will be appreciated, the present invention is also directed to a methodology for limiting access to data stored on an optical medium. While both the optical disk of the present invention and the methodology for utilizing

10

15

20

25

30

35

the same in a computer's optical readout system is described herein with reference to a conventional CD ROM disk, the ordinarily skilled artisan would readily appreciate that the teachings of the present invention may also be applied to other types of optical disks, such as audio CD's, WORM (Write Once Read Many) optical disks, and DVD (Digital Versatile Disks), to name only a few.

With this in mind, then, a typical optical readout system 10 of a computer incorporating an optical disk according to the first exemplary embodiment of the present invention is introduced in Figs.1 and 2. Optical readout system 10 broadly includes a disk drive 12 which is operative to rotate an optical disk 50 at a selected rotational speed, a light source 20 for producing an interrogating beam of light and a detector 40 which is operative to collect a returned component of the interrogating beam and to produce an output signal correlated to this returned component.

More specifically, and as is known in the art, disk drive 12 includes a motor 14 comprising a drive shaft 16 and a spindle 18 to which the CD-Rom optical disk 50 is mounted, and this motor 14 operates to constantly vary the rate at which the optical disk 50 is spun so that, regardless of where detector 40 is located in relation to the radius of optical disk 50, the portion of disk 50 located immediately above detector 40 is always moving at the same rate. Unlike conventional magnetic disks, which are divided radially into sectors and spin at a constant angular velocity, data on a CD-Rom disk is contained in a single track that spirals from the center of the disk to This track is still divided into its circumference. sectors, but each sector is the same physical size. Using a method known as constant linear velocity, the disk drive 12 constantly varies the rate at which (optical disk) 50 spins so that as detector 40 moves toward the center of the

10

15

20

25

30

35

optical disk 50 the disk increases its rotational speed. The effect of this is that the optical disk 50 can contain more sectors than a conventional magnetic disk and, consequently, more data.

Light source 20 generates an incident or interrogating beam of light via laser diode 22 and this beam 23 is initially collimated by collimator 26. The collimated beam is then directed toward a polarized beam splitter, or prism 28, after which it is sent through a quarter wave plate 30. Alternatively, for optical readout systems wherein the laser diode 22 and collimator 26 are offset in position relative to beam splitter 28, a wedge mirror prism may be employed to direct the beam in an axial direction relative to optical disk 50. After collimated beam 24 encounters quarter wave plate 30 it is thereafter directed through an objective lens 32 and an appropriate focusing coil to produce a concentrated and focused interrogating beam 25.

Focused interrogating beam 25 penetrates substrate 52 of optical disk 50 and typically strikes a metallic reflective layer 56 that is coated on the substrate 52. Metallic layer 56, itself, is encoded with information stored as a plurality of data structures 58 and is specifically contoured to include a sequence of lands 57 and pits 59 which define these data structures 58. may be accomplished with a conventional stamping process wherein metallic layer 56 is pressed into substrate 52 to create pits 59. Lands 57 are those areas which are not pressed and remain in their original position. Metallic layer 56 is approximately 1 micron thick and pits 59 are, by design, only one quarter wavelength of the wavelength of interrogating beam 25. Lands 57 and pits 59 correspond to the l's and O's used to store data information. interrogating beam 25 from laser diode 22 is focused at the surface level of lands 57, as shown. Whereas, light that strikes a pit 59 is scattered, light that strikes a land 57

15

20

25

30

is reflected as a returned beam 27 and directed back through polarized beam splitter 28. Beam splitter 28 deflects the returned beam 27 towards a tracking error detector 42, which controls tracking and focusing of the laser beam to sub-micron levels, and ultimately to light detecting photo diode 44. Light that strikes photo diode 44 generates a small electrical voltage at electrical leads 46, 48 and these voltages are matched against a timing circuit to generate the stream of 1's and 0's that the computer can understand. Accordingly, photo diode 44 converts the presence or absence of lands into an electrical signal.

The construction of a first exemplary embodiment of optical disk 50 may better be appreciated now with reference to Fig. 3(a) which is an exploded view of area "A" in Fig. 2. Optical disk 50 is constructed somewhat similarly to CD-Rom disks or audio compact disks now available. That is, as discussed above, optical disk 50 includes a substrate 52 and a metallic layer 56 upon which a protective coating 54 is placed. The metallic layer 56 is formed so that it is encoded with the information stored thereon as the plurality of data structures 58 that are readable by interrogating beam 25. Substrate layer 52, which may be formed out of polycarbonate, is disposed in a confronting relationship with metallic layer 56. As shown, metallic layer 56 is interposed between a lower surface 55 of protective coating 54 and substrate 52.

Unique to the present embodiments of the invention, though, is the inclusion of a film of reactive compound 60 that is superimposed over at least some of data structures 58. This reactive compound 60 is selected to be of a type which is operative to change physical characteristics in response to a selected stimulus, and thereby to affect readability of the information by interrogating beam 25.

10

15

20

25

30

In this first exemplary embodiment of optical disk 50, reactive compound 60 is formed as a coating on a lower surface 51 of substrate 52. In alterative embodiments, the reactive compound may be:

- (a) interposed between the metallic layer 56 and the inner surface of substrate 52 as discussed more thoroughly below with reference to Figs. 7A-7D, or
- (b) embedded within the substrate 52. The selected environmental stimulus to which the reactive compound responds, regardless of its location in the optical disk, will also be discussed more thoroughly below with reference to certain classes of chemical materials from which the reactive compound may be chosen. Briefly, however, for each environmental stimulus to which the reactive compound responds, the reactive compound changes its optical transmission characteristics from an optically transparent condition to an optically opaque condition whereby it masks the data structures and affects the integrity of the electrical signal generated by the computer's optical readout system.

For example, Figs. 3A and 3B illustrate how the integrity of the optical readout system's electrical signal is affected when the interrogating beam 25 encounters a land 57. As shown in Fig. 3A, interrogating beam 25 initially is able to penetrate both the reactive compound 60 and substrate 52 to detect the presence of land 57, which for purposes of discussion only, may correspond to data information in the form of the binary 1. Accordingly, interrogating beam 25 is reflected off of metallic (reflective) layer 56 as a returned beam 27 which is thereafter detected by light detecting photo diode 44, resulting in the generation an electrical signal correlated to land 57.

However, and as may now be seen with reference to Fig. 35 3B, after an accumulated duration of time, a region 62 of

15

20

25

30

35

reactive compound 60 changes its physical characteristics to an optically opaque condition whereby interrogating beam 25 is absorbed by the reactive compound 60 and is no longer able to penetrate the substrate 52 to detect the presence of land 57. Therefore, light detecting photo diode 44 does not receive a returned beam, as expected, and generates an improper electrical signal to the computer. As far as the optical readout system 10 is concerned, the interrogating beam 25 is positioned directly beneath a pit as opposed to a land, resulting in an incorrect data transferred to the computer.

Figs. 4 and 5A-5B illustrate the situation where interrogating beam 25 is positioned directly beneath a data structure 58 in the form of a land 57. It may be appreciated that, here, light source 20 has been advanced either radially or circumferentially across the outer surface 51 of substrate 52 to a different location as dictated by the computer's program. Looking at the exploded area A' in Fig. 5A, it is seen that interrogating beam 25 is initially able to penetrate both reactive compound 60 and substrate 52 and impinge upon metallic layer 56 which coats land 57. Because reflective material 56 in this region is not positioned at the level of the interrogating beam's focal point, interrogating beam 25 is Thus, either no returned beam is reflected or scattered. an insufficient amount of light is reflected back to photo diode 44, thereby resulting in the generation of a binary electrical signal by detector 40 which corresponds to the presence of the encountered pit 59. This is the expected result.

After an accumulated duration of time, the region 62 of reactive compound 60 which is exposed to interrogating beam 25 becomes darkened or opaque. Light in this region 62 is absorbed and not allowed to penetrate substrate 52 to detect the presence or absence of pit 59.

10

15

20

25

30

35

The result is, therefore, the same in that detector 40 generates a binary electrical signal, such as a zero, corresponding to the presence of a pit.

A second exemplary embodiment for the optical disk according to the first collection of embodiments may now be appreciated with reference to Figs. 6A - 6B and 7A - 7B. Here, the reactive compound 160 of optical disk 150 is shown to be interposed between the substrate 152 and metallic layer 156. While it is inherently more difficult to manufacture optical disk 150 than it would be to manufacture optical disk 50 which is referenced in the first exemplary embodiment of the present invention, the construction of optical disk 150 may be preferred from a performance standpoint because reactive compound 160 is located in a region where interrogating beam 125 would have a greater beam intensity than would beam 25 due to its relatively reduced focal width in this region. practical purposes, however, the results would nonetheless be the same.

For example, Fig. 6A again illustrates the situation where interrogating beam 125 is positioned beneath a land 157 such that the beam is reflected off of metallic layer 156 as a returned beam 127 which would be recognized by the detector and correctly converted into a corresponding binary electrical signal. In Fig. 6B, on the other hand, it is shown that after an accumulated duration of time, the region 162 of reactive compound 160 which has been exposed to a given environmental stimulus changes its physical characteristics from an optically transparent condition to an optically opaque or darkened condition. interrogating beam 125 is absorbed in region 162 and no returned beam is detected, resulting in the generation of a binary electrical signal by the computer's optical readout system, despite the presence of pit 159. In Figs. 7A - 7B the situation is similar to that discussed above

15

20

25

30

35

with reference to Figs.5A - 5B. Thus, when interrogating beam 125 is positioned directly beneath a pit 159, the computer's optical readout system would generate the proper binary electrical signal irrespective of the physical characteristic of reactive compound 160 in region 162.

#### A. Classes of Materials For the Reactive Compound

Various classes of materials have been found which exhibit appropriate physical characteristics for utilization in the optical disk according to the exemplary embodiments of the present invention. Each of these materials responds to either a specific environmental condition, or a combination of environmental conditions, to mask the data structures on an optical disk, thereby affecting their readability by the computer's optical readout system.

#### 1. Photo Reactive Compounds

It has been found that photoreactive materials exhibit desired light absorption characteristics and that these materials may be formed as a coating on an optical disk to mask at least some of the disk's data structures from detection by an optical readout system. Photochromes, and specifically the spiropyran class of photochromes, have Photochromism is the phenomenon particular utility. whereby the absorption spectrum of a molecule changes reversibly or irreversibly when the sample is irradiated by light having certain wavelengths. For example, a colorless compound can change to a quasi-stable colored structure when it is irradiated with infrared light. While a specific photochromic or photosensitive material of the spiropyran class is discussed herein for use in the present invention, the ordinarily skilled artisan would appreciate that other photochromic materials such as aziridine derivatives, diohydropyrene bipyradine derivatives, derivatives, fulgide derivatives, thioindigo derivatives, azobenzene derivatives, salicylideneaniline derivatives,

xanthane derivatives, oxazine derivatives may also prove useful.

spiropyran class dye, having the chemical composition 6-nitro-1'3'3'-trimethylspiro-[2H-1benzothiopyran-2,2'-indoline], or 6-nitro-1-5-BIPS for 5 short, is discussed in Tarkka, Richard U. Talbot, Marc E., "Holographic storage in a near-ir sensitive photochromic dye." Optic Comm. 109, 54-58 (1994), the teachings of which are incorporated herein by reference. When exposed to infrared light having a wavelength of 10 approximately 780 nanometers (nm), a wavelength which is predominantly utilized in current optical readout systems, this dye becomes colored. The dye may thereafter be returned to its optically transparent state upon exposure to an ultraviolet source at approximately 337 nanometers 15 This ability to erase the color from the dye is not fatal in that it requires a relatively expensive and difficult to find light source. 6-nitro-l-S-BIPS is preferably applied as a coating to the substrate of an optical disk as illustrated in Figs. 3 - 5 above. With 20 derivative, other spiropyran or chromophores, it is recognized that the environmental is simply exposure to the light sources stimulus interrogating beam.

25 2. Compounds Which are Photoreactive in the Presence of Oxygen

Two materials which may also be used in conjunction with the optical disk according to the present invention are photoreactive in the presence of an ambient environment containing oxygen.

#### a. Compound I

30

One such material is denoted as compound I below:

10

15

25

**COMPOUND 1** 

Compound 1 is made by treating tetramethylindolium iodide with 10 Molar equivalents of 1N sodium hydroxide in water with good mixing. As compound I is formed, it is extracted into the hexane co-solvent according to the following reaction:

Tetramethylindolium iodide

COMPOUND 1

Alternatively, one molar equivalent of triethylamine in dichloromethane can be used and the product can be isolated by extraction with water, evaporation of a solvent and dissolution in hexane. The aqueous base method is preferred in that it yields in excess of 80% of the desired final product.

Compound I is photoreactive with oxygen and sensitive to ambient florescent light over several (> 18 hrs) exposure, is quickly (< -10 mins) photo oxidized upon exposure to an incandescent 150W lamp at a distance of 12 inches. Compound I also reacts upon exposure to light

## SUBSTITUTE SHEET (RULE 28)

10

15

20

25

26

having a wavelength of approximately 650 nanometers (nm) and an intensity approximating that of a digital versatile disk (DVD) player light source. Accordingly, compound I is useful for application to an optical disk incorporated in developed DVD drives.

#### b. Compound II

Another material which is photoreactive in the presence of oxygen can be made from quinoline salts and related enamine derivatives. This photoreactive material is denoted as compound II below and may be prepared, similarly to compound I, according to the following reaction:

With both compounds I and II above, it should be appreciated that the environmental stimulus which causes them to change in optical transmission is a combination of both light and oxygen. Moreover, these compounds are specifically adapted for use in a computer's optical readout system which utilizes a light source having a wavelength of 650 nanometers (nm). Because these compounds react to change their light absorption characteristics in the presence of an ambient environment containing oxygen, the required amount of time for such change varies depending upon the wavelength of the ambient light. It is, therefore, desirable that the optical disks coated with either compounds I or II, be packaged in an inert

### SUBSTITUTE SHEET (RULE 26)

environment and/or a standard hermetic packaging. To this end, Fig. 8 shows that such an optical disk 250 is preferably contained in a package 210 in the form of an aluminum bag coated with polyethylene. Contained within package 210 is an inert gaseous environment, such as argon, nitrogen, neon, helium, or other ambient gas.

#### c. Materials Which Are Oxygen Reactive

It has also been found that certain oxygen reactive materials may be used in an optical readout system having a light source at a selected wavelength. One class of such materials is based upon the reduced forms of the well known dye, methylene blue. The method of synthesis and the oxygen dependent reoxidation to form the colored form of the methylene blue dye is shown below:

15

10

5

20

Various reducing agents can be used to reduce methylene blue and its many derivatives, with zinc and acetic acid being one possibility. The color of methylene blue when reduced is pale yellow and it quickly is re-oxidized to be dark blue by oxygen in air. The rate of this reaction is somewhat dependent on the medium, however. In polyurethane films, this rate has varied from about 10 minutes to 30 minutes depending on the concentration. When sodium borohydride residue is not quenched in these films, they gradually turn from clear to blue over several hours. The

## SUBSTITUTE SHEET (RULE 26)

blue form of the methylene blue dye absorbs strongly at 650 nanometers (nm), the centered wavelength for DVD laser light readers.

Other dyes which are reactive in the air (e.g., to oxygen) perform similarly to the methylene blue and have maximum absorbencies that can vary by several tens of nanometers. The structures of some of these dyes known to perform like methylene blue and their commercial names are shown below:

10

5

15

basic blue 3

20

toluidine blue 0

Finally, for optical readouts systems employing an interrogating beam having a wavelength of 780 nanometers (nm), a wavelength which is predominantly used in CD-Rom readers, one dye has been shown to reoxidize over approximately 48 hours and thereafter absorb light at this wavelength. The synthesis and oxidation of this dye, denoted as compound III, is shown below:

It is certainly contemplated that numerous other similar dyes can be synthesized to operate effectively in a given optical readout system. With each of the air reactive materials discussed herein, as with those materials discussed above which are photoreactive in an ambient environment containing oxygen, it is desirable to package the optical disk containing the dye in an inert environment as shown in Fig. 8.

10

15

20

5

With an understanding of the various compounds which the reactive compound of the present invention may assume, the ordinarily skilled artisan in this field would readily appreciate that the particular compound selected would depend on a variety of parameters of the operating environment. Where a CD ROM application is preferred, the reactive compound would necessarily be one that is compatible with this environment, sensitive to the infrared lasers used in the CD-Rom's optical readout system (i.e. 650 nm or 780 - 830 nm) and will react to the lower powered intensity of the interrogating beam (approximately .15 to For those reactive compounds which are .6 mW of power. reactive in the presence of oxygen, a user would of course be careful to avoid exposure of the optical disk to an ambient environment containing either oxygen, or light and

SUBSTITUTE SHEET (RULE 26)

10

15

20

25

30

35

oxygen, in order to prolong the useful life of the optical disk.

A primary thrust of the present invention is, of course, to deny access to a specially coated optical disk, and preferably a CD-Rom disk, beyond one or more authorized To this end, one potential use for coating an optical disk with a reactive compound would be to allow for sample disks to be given away to customers in order for them to determine whether or not the product is worth Once the product has been evaluated, the purchasing. customer then might be required to return the product to the vendor and buy a commercial version of the sample In one novel application of the present optical disk. invention, such specially coated optical disks may have music encoded on them so that such disks are only playable for a particular period of time and/or for a particular number of times. Thus, optical disks that automatically expire are provided by the present invention. Moreover, note that movies and other multimedia presentations can be commercially provided in a similar fashion. Alternatively, a customer could purchase a coated optical disk and load it onto a computer's hard drive prior to the reactive compound changing its physical characteristics and rendering the optical disk unreadable.

Another potential application is the rental of optical disks which contain the reactive compound. Such an optical disk may be rented, much like videos cassette at a low cost and played until such time as the optical readout system of the disk player is no longer able to detect the presence or absence of the encoded information.

As shown in Fig. 9, the reactive compound may be applied to the optical disk in a variety of patterns. Fig. 9, of course, only illustrates a few such applications and others are certainly contemplated without departing from the concepts of the present invention. To illustrate,

10

15

20

25

30

35

reactive compound 260 may be embossed as a film over an entire sector of optical disk 250, such as representative sectors 252 and 254. Alteratively, the reactive compound 260 may be applied to only a portion of a sector, such as region 256 in Fig. 9. Although, the entire surface of optical disk 250 could be coated with reactive compound 260, this is not a necessity, because the compound could merely be applied to that portion of the disk which contains critical information for the optical readout system to access in order for the software product to function properly. With specific reference to the spiropyran class of photochromes discussed above, it is also anticipated that a reactive compound of this type, which is adapted to reversibly change between a darkened colored state and a transparent state, could be initially be applied in its darkened state to the surface of the A software application residing on an optical disk. optical disk for the present invention may execute properly only in the event that the optical readout system continues to process information as if no data were contained in this region. Once the photochrome changes to the transparent condition upon sufficient exposure to light, the optical readout system would be able to detect the plurality of and the software application then structures, discontinues its proper function.

With the foregoing in mind, the first collection of embodiments of the present invention is directed to an article of manufacturer adapted to be encoded with data and further adapted so that duplication of the data by an optical scanning machine may be restricted. To this end, the article of manufacturer comprises a substrate fabrication from a selected material and having a substrate surface which contains the data. A reactive compound is formed as a coating on at least a portion of the substrate surface and this reactive compound is operative to change

10

15

20

25

30

35

from an optically transparent state to an optically opaque state in response to a irradiation for an accumulated duration of time by light having selected characteristics, thereby to prevent the light from the optical scanning machine from penetrating the reactive compound and to render the data undetectable by the machine.

It should also be appreciated from the foregoing that another aspect of the present invention is a methodology of limiting access to data stored in an optical medium according to the first collection of embodiments. Broadly, this methodology comprises the steps of rotating an optical disk in a disk drive at a selected rotational speed, with the optical disk including a substrate and a metallic layer encoded with information stored thereon as a plurality of readable data structures and including a reactive compound superimposed over at least some of these data structures. compound is operative in an ambient reactive oxygen optical to change environment containing transmission in response to irradiation for an accumulated duration of time by light having a beam wavelength that is The broad methodology would also within a selected range. include a step of directing an interrogating beam of light having a beam wavelength that is within the selected range toward the substrate and through the reactive compound for the accumulated duration of time.

The step of directing the interrogating beam of light could be accomplished by directing the beam toward the substrate for a continuous interval of time that is sufficient to cause the change in optical transmission. The methodology also contemplates that the interrogating beam can be directed at the substrate for a plurality of discrete intervals of time sufficient to cause the change in optical transmission. This might occur, for example, where the light source of the computer's optical readout system selectively advances the interrogating beam radially

10

15

20

25

30

35

across an outermost surface of the optical disk until the beam interacts with the reactive compound for the plurality of discrete intervals of time. It is preferred that the methodology be practiced with a beam wavelength approximately either 780 or 650 nanometers (nm) and a beam intensity of approximately 0.14 milliwatts (mW) 0.6 mW of power.

In Figs. 10A, 10B and 10C, a representative flowchart is provided of the steps performed in the method of the present invention according to the second collection of described in the summary embodiments as That is, the flowchart of these figures hereinabove. illustrates the steps performed to prohibit unrestricted duplication and/or access of information on an optical medium or disk manufactured according to an embodiment of the present invention. In particular, the present method provides for purposefully inducing a physical change to the optical disk during its use; i.e., the physical change may be caused substantially automatically by, the the optical disk, software on activation of alternatively may be caused as a purposeful effect of manual action by the user. More particularly, flowchart of Figs. 10 illustrates the steps performed when installing software on a user's computer from an optical disk configured according to the present invention. in step 1000, the user inserts the optical disk into the optical disk drive (also denoted optical readout system or optical reader hereinabove). Subsequently, in step 1004, the user initiates or activates a start-up or installation program for processing information on the optical disk during an installation of the software on the optical disk. Note that this installation program may be read from the optical disk as a first portion of the information read. Alternatively, this installation program may be downloaded Upon activating the installation from the Internet.

10

15

20

25

30

35

program, the user may be allowed the option of either activating a demonstration version of the optical disk software wherein a manual change to the optical disk is not Assuming such an option is available, in step 1008, a response from the user is solicited as to whether the user desires to use a demonstration version of the example, prior to performing a full for software, installation on the user's computer. Accordingly, assuming the user requests to use a demonstration version, steps 1012 through 1020 are performed, wherein a demonstration version of the software may be loaded onto the user's computer thereby allowing the user to perform, for example, a restricted set of features of the optical disk software application.

Alternatively, if in step 1008, the user desires to fully install the software application from the optical disk, then step 1024 is performed, wherein one or more decryption procedures are installed into the user's computer from, e.g., the optical disk or the Internet. Note that at least some of the information residing on the optical disk is encrypted so that it is not easily duplicated as a non-executable sequence of bits or characters, and subsequently reverse engineered to obtain a fully functioning executable version of the software on the optical disk. Thus, it is to be understood that in the subsequent steps for installing the application software from the optical disk to the user's computer, that the encryption procedures installed in this step (1024) are activated one or more times for decrypting at least some crucial information transferred between the optical disk and the user's computer.

Subsequently, in step 1028, a determination is made as to whether a predetermined area of the optical disk has an occurrence of a profile of an expected physical change to the optical disk. That is, the start-up program assumes

10

15

20

25

30

35

that the optical disk is in a particular predetermined physical configuration or state when obtained from the manufacturing process, and during this step, the start-up program determines if the physical characteristics of the optical disk conform to this assumed initial state or whether an occurrence of a particular profile of an expected physical change has occurred. In particular, note that the expected physical change, if detected, is assumed to be due to a previous installation of the software of the optical disk.

It is worth mentioning that such an expected physical change during such a software installation procedure may be due to any one of a number of user initiated techniques. For example, an additional layer or substance can be incorporated into the optical disk in a predetermined area so that upon purposeful removal by the user of the layer or substance (either mechanically or chemically), the optical information coinciding on the optical disk with this layer is changed in an expected arrangement so that in a subsequent installation attempt, this expected arrangement In particular, examples of such can be detected. techniques are discussed hereinbelow and illustrated in in another 11A through 14B. Alternatively, technique, an external device may be utilized by the user to intentionally change a predetermined portion of the optical disk as described hereinbelow with reference to In yet another technique, a Figs. 15A through 16B. predetermined portion of the optical disk can be initially provided with an additional coating or layer that distorts or hides a predetermined portion of the optical disk information so that upon first use of the optical disk for installing the software therein, this layer is either removed or changed in some fashion so that the information encoded underneath is capable of being read by the optical disk reader. In particular, this technique is described

10

15

20

25

30

35

and illustrated hereinbelow with reference to Figs. 17A through 21B. However, for each such technique it is an aspect of the present invention that in most embodiments the predetermined portion of the optical disk having an intentional change is limited to a minority of the storage capacity of the optical disk.

in one important class of embodiments Moreover, wherein the expected physical change is due to a change in the errors detected (e.g. either an increase or a decrease in errors), additional steps may be performed by software implementing the flowchart of Figs. 10 wherein these additional steps activate and deactivate the optical disk error correction module(s) of the user's computer system. Note that this becomes an important time saving aspect of the present invention in that considerable time can be consumed by the error correction module(s) in attempting to read purposefully induced unreadable errors. deactivating the error correction module(s) just before a determination of whether an occurrence of an expected profile of errors is made (i.e., just before steps 1028 and 1052 of Figs. 10), and subsequently reactivating the error correction module(s) immediately thereafter, considerable time may be saved in, for example, (re)installing software from the optical disk, activating a presentation of a movie from the optical disk, etc.

Returning now to the steps of the flowchart of Figs. 10, assuming that in step 1028 the expected change from the original optical characteristics of the optical disk is not detected, then step 1032 is performed wherein the installation procedure may request user specific data such as the user's name and/or other user identifying information. Following this step, in step 1036, the installation procedure may install substantially all the software from the optical disk with the exception of one or more portions that are necessary for activating the

10

15

20

25

30

35

software. Subsequently, in step 1040, the installation process sets internal flags indicating that an initial full installation of the software is in progress. This step provides a substantially failsafe feature of the present invention so that if there is a computer failure during installation, these internal flags can be subsequently detected in the persistent storage (e.g., the hard disk) of the user's computer, and subsequently used to reinitiate the installation procedure. Subsequently, in step 1044, the user is instructed to remove the optical disk from the computer and physically modify the optical disk in a predetermined manner and subsequently reinsert the optical disk into the computer.

Assuming that the optical disk has been reinserted, in step 1052 the installation procedure determines whether an expected profile of a physical change to the optical disk has occurred in a predetermined area of the disk. particular, various embodiments of the present invention determine the physical change in the optical disk by analyzing a change, for example, in the errors generated when attempting to read certain predetermined locations on the optical disk. For instance, the change may be detected (a) a total number of errors generated in a sampling of locations in an area of the optical disk (e.g., a detected number of errors greater than a minimum threshold, or less than a maximum threshold), (b) a density of errors generated in a sampling of locations in an area of the optical disk (e.g., a detected density of errors greater than a minimum threshold or less than a maximum threshold), (c) a relative number of errors generated in a sampling of locations in an area of the optical disk, (d) a pattern of errors generated in a sampling of locations in an area of the optical disk, (e) a statistical analysis of the errors in a sampling of locations generated in an area of the optical disk, (e.g., a regression analysis). Moreover,

10

15

20

25

30

35

instead of determining various measurements related to errors detected, the physical change in the optical disk may be detected by computing a measurement related to the non-error generating locations of an area of the optical Thus, by replacing the word, "errors", with the word, "non-errors" in (a) through (e) above, additional examples for detecting a change to the optical disk are obtained. Further, note that the change may be detected stochastically wherein, for example, a probability or likelihood measurement is computed for determining whether a change has been detected. Note that the physical change may be removing, replacing or rearranging an entire wedge extending through all layers of the optical disk. instance, a tab on an edge on an optical disk may be broken from the optical disk as part of an initial installation. Moreover, in some embodiments, such errors are not only detectable, but they are also not capable of being corrected by error correction circuitry since the errors are so prevalent. However, it is also within the scope of the present invention to detect such a change by other techniques than error detection. For example, a detachable optically readable layer may mask alternative optically removing (and/or Thus, by information. readable rearranging) the detachable optically readable layer and exposing the alternative data, a change to the optical disk can be detected.

Referring again to step 1052 of Fig. 10C, if an expected profile of the requested physical change to the optical disk has not occurred, then the installation procedure terminates (i.e., the "no" branch is taken). However, assuming that such a profile of an expected physical change is detected, step 1056 is performed wherein the installation process determines a collection of characteristics that uniquely identify the computer and the optical disk combination. For example, characteristics

10

15

20

25

30

35

relating to the user's computer may be various serial numbers associated with the central processing unit, and other peripheral processors or devices. Additionally, characteristics, the optical disk regarding installation software samples the detected changes to the optical disk in the predetermined area and subsequently encodes the locations of the changes in this predetermined area by generating one or more codes related to the optical readability of the disk in the predetermined area. by combining the characteristics of the user's computer with the encoded characteristics of the physical change to the optical disk and possibly an encoding of the user data entered, a unique encoded identifier can be generated as, e.g., a character string as described in step 1060. Note that hereinafter the unique identifier will be denoted as a "configuration fingerprint." As an aside, note that it is important that the unique physical characteristics of the optical disk be encoded into the configuration fingerprint since otherwise there is the potential for a user to use a configuration fingerprint based solely on the characteristics of the user's computer to install software from optical disks of the present invention on any number of computers.

In step 1064, the configuration fingerprint is written into persistent storage on the user's computer, and additionally, the configuration fingerprint is output to the user. Subsequently, in step 1068, the installation procedure instructs the user to remove the optical disk from the computer and manually write the configuration fingerprint on the optical disk. Additionally, as described in step 1072, the user is instructed to enter the configuration fingerprint as written on the optical disk as input into the user's computer. Note that the entering of the configuration fingerprint by the user and the subsequent checking to determine whether the computed

15

20

25

30

35

configuration fingerprint and the one entered by the user are identical provides a level of assurance that the configuration fingerprint written on the optical disk is identical to the computed configuration fingerprint. during subsequent since а important assurance is reinstallation attempt from the optical disk. the configuration fingerprint is recomputed and a match with a user input fingerprint is required before the software will be (re)installed on the user's computer.

Assuming that eventually the configuration fingerprints match in step 1076, step 1080 is performed wherein the installation procedure completes installation of the software from the optical disk.

Returning now to step 1028, if the installation procedure determines that in a predetermined area of the optical disk, there is indeed an occurrence of a profile of optical the original expected change from an characteristics of the optical disk as manufactured, then wherein configuration 1084 is performed the step fingerprint for the optical disk is computed as in the steps 1056 and 1060. Following this step, in step 1088, is instructed to enter the configuration the user fingerprint written on the optical disk. Thus, in step 1092, the installation procedure determines whether the computed configuration fingerprint matches the input provided bv the user. configuration fingerprint Accordingly, if these two fingerprints do not match, then the installation procedure quits without fully installing the software. Alternatively, if the fingerprints, match, then the remaining portion of the installation completed.

It is worth noting, however, that even though the software of the optical disk may not be able to be installed at a computer different from the initial installation computer, it is an aspect of the present

15

20

25

30

35

invention that the software may be executed directly from the optical disk in the case where the software cannot be installed due to, for example, a mismatch of configuration fingerprints as determined in step 1092 above. That is, it is an aspect of the present method that the user may be able to execute the software of the optical disk on any computer capable of reading the disk by executing the software directly from the disk.

In some embodiments of the present invention, the configuration fingerprints may not be required to exactly match in order for a complete reinstallation (step 1096 above) to be performed. In particular, it is an aspect of these embodiments of the present invention that as long as the configuration fingerprints are sufficiently similar, the installation process of step 1096 is performed. Thus, if the optical disk becomes scratched accidentally in the predetermined area where the expected change is to occur, and certain components of the user's computer were replaced, then the user may still be allowed to install the software on the optical disk due to a sufficient similarity between the computed configuration fingerprint and the input configuration fingerprint.

Referring now to Figs. 11A - 21B, a second collection of embodiments (denoted hereinafter as the "manually activated embodiments") of the present invention are illustrated. Accordingly, these embodiments, as with the previous embodiments described, prohibit unrestricted duplication of information on an optical disk manufactured according to the present invention. However, in the manually activated embodiments, the user manually effects a physical change to the optical disk during an initial use so that this change can be detected upon subsequent uses of the optical disk. Thus, as with the previous embodiments that automatically change optical states when irradiated by an optical scanning machine, there is protection against

10

15

20

25

30

copying, duplication, unauthorized installation or use of the data on the optical disk.

In Figs. 11A - 12, a first of the manually activated embodiments is illustrated. In the embodiment illustrated in these figures optical disk 1150 includes painted surface 1154 and protective lacquer layer 1158 as the uppermost surfaces. Additionally, as is typical for such disks, there is also a metalized or reflective layer 1162 and a transparent polycarbonate layer 1166. To these layers the present invention provides an extra or additional assembly 1170 for purposefully generating an expected profile of read errors on the optical disk 1150 (this additional assembly 1170 is hereinafter also denoted as a "ripcord") when this assembly is, for example, mechanically removed.

In the present embodiment, the ripcord 1170 includes (a) a substantially tear resistant patch 1174 (best shown in Fig. 11B) embedded within the optical disk 1170, and (b) a pull tab 1178 that is firmly attached to the patch 1174. Note that in the present figure there is a bonding layer 1182 bonding the patch to the reflective layer 1162. However, in general, the patch 1174 is attached or otherwise bonded to at least one of the sides of the metalized layer 1162 and/or lacquer layer 1158 of the optical disk 1150. For instance, the patch 1174 may be screwed, glued, welded, soldered, clipped or laminated onto the optical disk 1150. Moreover, the patch 1174 and/or the pull tab 1178 may be made of metal, plastic, wood or other suitable material that does not tear easily under tension. The patch 1174 may also be manufactured as part of another layer of the optical disk 1150; e.g., the reflective layer 1162.

Note that there can be various embodiments of a ripcord 1170 that can be mechanically manipulated to provide a physical change to an optical disk of the present

15

20

invention. For example, such mechanical ripcords can be in the form of:

- (1.1) a laminated layer with a pull tab
  (substantially as shown in Figs. 11A, 11B);
- (1.2) an error generating push or twist button (not shown) having, for example, a particular arrangement of pins or other pointed objects that etch or scratch a surface of the optical disk 1150 when pressure and/or a twisting force is applied;
- 10 (1.3) a sticker, a strip of metal, an adhesive tape, a pin or other similar object that is effective for generating data access errors when detached from the disk.
  - Accordingly, when such a ripcord 1170 is removed (Fig. 12) from the optical disk or in some way moved or disturbed, the ripcord 1170 also removes, moves, damages and/or carries away with it and/or otherwise modifies the reflective characteristics of the optical disk 1150 so that the data structures thereon generate an increased number of read errors when a read access is attempted. That is, an optical reader (such as an optical readout system 10) is then unable to detect and/or access the information which is present at or near where the ripcord 1170 was located on the optical disk 1150.
- In Figs. 13A 14B, another embodiment of a ripcord is 25 shown, this being a "chemical ripcord" 1370 provided on wherein this disk has disk 1350, corresponding to those of optical disk 1150; i.e., painted surface 1154, lacquer layer 1158, reflective layer 1162 and The chemical ripcord 1370 is polycarbonate layer 1166. 30 incorporated into the optical disk 1350 as an ampule, globule, sac, macroscopic or microscopic chemical carrying liposome made of plastic, wood, metal or other suitable material that can be attached, bonded, glued or laid upon the optical disk as part of the manufacturing process. For 35

10

15

20

25

30

35

example, referring to Figs. 14A and 14B, when pressure is applied (e.g., as represented by force vector 1404), this chemical ripcord is ruptured (or moved, touched, rubbed, or otherwise disturbed) as shown in Fig. 14B. Subsequently, the chemical(s) within is released and/or activated for purposefully damaging the optical disk 1370, and in particular the reflective layer 1162, so that, for example, a greater number (or density or pattern) of optical disk read errors are generated in the area or location adjacent to the now disturbed chemical ripcord 1370. Thus, assuming an optical reader is enabled to detect and/or access the information corresponding to the data structures which are present at or near the location of the chemical ripcord 1370, the optical reader and/or application software associated with the present invention (e.g., as described in Fig. 10) can detect that the information near or adjacent to this location has changed state (e.g., from readable to unreadable) and accordingly, use this state change information for determining subsequent access and/or use of the information residing on the optical disk 1370 as, e.g., is described in Figs 10.

In Figs. 15A - 16B, two additional ripcord techniques for purposefully damaging an optical disk are illustrated, wherein a device external or unattached to the optical disk is used. Accordingly, the optical disk 1550 represented in the presently referenced figures may be a conventional optical disk with the possible exception that the painted surface 1154 may provide an indication as to where the optical disk is to be purposefully damaged. One such disk damaging technique is illustrated that uses an external device 1554 having, for example, a sharp point that can be used for mechanically and purposefully etching, scratching or otherwise damaging the optical disk 1550 as illustrated in Fig. 15B. Referring now to Figs. 16A and 16B, an alternative disk damaging technique is illustrated for a

10

15

20

25

30

35

disk such as 1550. That is, in this technique, a device 1654 that is external or separate from the optical disk 1550 is used for applying a particular chemical(s) 1658 that can purposefully damage at least a portion of the optical disk 1550 so that changes to its reflective characteristics are detected by an optical disk reader. particular, the external device 1654 disclosed has an enclosed chemical compartment 1662 from which chemical(s) 1658 are applied to the optical disk 1550, wherein the chemical(s) reacts with the optical disk 1550 for removing or damaging the reflective characteristics of the optical disk so that a greater number of read errors are generated in a predetermined area where the chemical(s) is applied.

Accordingly, in the embodiments of Figs. 15 and 16, an optical reader may be unable to detect or access a substantial amount of the information corresponding to the data structures at or near the use of the external device. Also, the optical reader (and/or other components or modules used in the accessing or processing of information from the optical disk 1550) may determine that the information on the optical disk has changed states (e.g. an indication of a prior use) according to the access errors detected in the predetermined area where the external device was applied (as in step 1052, Fig. 10B).

Additionally, note that an external device as 1554 or 1654 may also include a pin (or other sharp instrument) for both physically and chemically damaging the disk. other embodiments for purposefully damaging an optical disk are also within the scope of the present invention. example, the following may be used: a pad, a scratch inducing swatch, or, in a chemical application embodiment, a liposome carrying paste, a receptacle for holding two or chambers for separate chemical compounds in more purposefully damaging (more generally, changing) optical

10

15

20

25

30

35

characteristics of the disk when the two or more compounds are combined.

Thus, as described in Figs. 10, once the optical disk is physically changed, altered or otherwise damaged (e.g., step 1044, Fig. 10B) by any of the above techniques, separately or in combination, the user's computer system may then determine the extent to which the information on the optical disk can be accessed or used in a user desired That is, the change and/or damage to the optical disk provides a recognizable state change to, for example, installation routines (e.g., access associated with the optical disk and/or any software application thereon so that a determination can be made as to whether the information on the optical disk has been previously accessed. In addition, such a change and/or damage to the optical disk also provides a user with a visible indication that the data on the optical disk has been accessed. More generally, the purposefully altering or changing of the optical disk provides a mechanism for determining a history of the use of the optical disk, both computationally and by visual inspection of the optical disk.

In Figs. 17A - 21B, converse embodiments to the purposefully damaging embodiments above are illustrated. That is, instead of the ripcord removing information from the optical disk (when the ripcord is manipulated and/or activated), the ripcord in the present embodiments allows additional or different optical disk information to become available (i.e., readable) when the ripcord is manipulated or activated. Thus, in these converse embodiments, instead of the read errors increasing according to an expected profile in a predetermined area of the optical disk, the read errors may decrease according to an expected profile. That is, the ripcord may initially hide or mask the information on the optical disk with a substantially

10

15

20

25

30

35

unreadable covering. However, it is also within the scope of the present invention that such a ripcord covering may be readable and provide different information than that on the optical disk. For example, an optical disk may contain one or more movies for viewing and the ripcord itself may provide information necessary for allowing the movies to be Thus, once the ripcord is removed, thereby viewed. providing access to alternative information, the movie(s) Thus, in this embodiment, a may be viewed only once. detection of a state change is performed without necessarily detecting an expected profile related to generated access errors. It is also worth mentioning here that, as one skilled in the art will understand, similar capabilities may be provided with other duplication protection embodiments of the present invention. example, by using an optical disk coating that changes from opaque to transparent due to, e.g., laser light from an optical disk reader, purposefully masked information on the optical disk can become readable and concomitantly causing a reduction in the number of errors detected and therefore providing a detectable state change in the optical disk.

Referring now specifically to Figs. 17A and 17B (where an optical disk 1750 is shown having similar layers labeled similarly to previous figures), a ripcord is attached or bonded to the exterior surface of the polycarbonate 1166 of an optical disk 1750; e.g., the ripcord 1770 may be laminated, screwed, glued, welded, soldered or clipped to the optical disk 1750. Moreover, the ripcord 1770 may include metal, plastic, wood, paper or other suitable material for hiding information encoded on the reflective layer 1182 of the optical disk 1750. Additionally, note that the ripcord 1770 may be manufactured as part of the optical disk, and can be in the form of a button, sticker, metal strip, adhesive tape, paper patch or other optical disk information mask (or optical distorter) capable of

10

15

20

25

30

35

being removed or rendered transparent to the laser light of the optical reader. Accordingly, when the ripcord 1770 of the present embodiment is removed (Fig. 18) from the optical disk 1750 or in some way moved or disturbed, additional (or alternative) information on the optical disk 1750 becomes readable. Thus, an optical disk reader is then able to detect and/or access this information at or near the previous ripcord location on the optical disk.

Note that additional converse embodiments may also be provided using a chemical approach. Referring to Figs. 19A and 19B (where an optical disk 1950 is shown having similar layers labelled similarly to previous figures), a ripcord 1950 herein includes a chemical carrying container (e.g., an ampule, globule, sac or liposome) attached, bonded, glued or combined with the optical disk 1950 during manufacture. Accordingly, as illustrated in Fig. 20, when this chemical container is removed, disturbed or ruptured, the enclosed chemical(s) is released and/or activated for modifying the reflective characteristics of the optical disk 1950 so that this information becomes readable. example, the chemical sac of the ripcord 1970 may be glued to the exterior surface of the polycarbonate layer with an opaque or colored glue, wherein the chemical(s) within the chemical sac is a solvent for the glue thereby allowing the chemical sac and the glue to be removed when the sac is ruptured and the solvent released. Thus, an optical reader subsequently able to detect and/or access information corresponding to the data structures on the optical disk 1450 which are present at or near the previous location of the ripcord 1970 on the optical disk. Moreover, such a change to an optical disk allows the optical reader (and/or other optical disk accessing components or modules) as well as a person, via visual inspection, to determine that a state change has occurred to the optical disk 1950.

10

15

20

25

30

35

In Figs. 21A and 21B, an embodiment of the optical disk 1750 (Figs. 17) of the present invention is illustrated wherein an external device 2104 is used for applying a chemical(s) to the optical disk, thereby removing the mask or ripcord 1770 attached to the surface of the optical disk 1750 so that optical disk information hidden by the ripcord 1770 is able to be read. Note that the external device 2104 here can be in the form of, for example, a pin, pad, swatch or liposome carrying paste or liquid, wherein the ripcord is either rendered transparent or removed.

In a third collection of embodiments of the present invention, an authentication method and apparatus are provided for authenticating an optical disk. Embodiments of this third collection provide optical disks with purposefully-induced data access errors incorporated therein during manufacturing or at least prior to mass distribution. Moreover, also included in each individual optical disk is authentication information indicating the location of these purposefully induced errors. Thus, when the authentication information accurately identifies the locations of the purposefully induced errors, then the optical disk is assumed to be authentic rather than an illegitimate copy. Note that one particularly noteworthy embodiment in this third collection is provided by attaching "microdots", i.e., microscopic unreadable dots or patches, at various locations throughout the information encoded on an optical disk. Accordingly, if the microdots are sufficiently small so that they obscure or distort only a small area of the optical disk (e.g., approximately 300 microns) then error correction circuitry included within an optical disk access device may be able to correct such errors transparently to a user of the optical disk. Alternatively, for many applications, such as audio (e.g., musical) presentations, the optical disk

10

15

20

25

30

35

information is encoded on the disk redundantly. Thus, even larger microdots may be incorporated without affecting the quality of a presentation of the information accessed from the optical disk.

In a fourth collection of embodiments of the present invention, effectively non-reproducible transaction cards for financial transactions can be provided by the present invention. That is, an optical medium (such as a portion of an optical disk material) is provided on a transaction card along with a mechanism, such as a ripcord, for purposefully damaging the optical medium. Thus, prior to issuing such a transaction card to a user, the optical purposefully damaged, and the financial medium institution stores an encoding of a mapping of the damaged of the optical medium. and/or undamaged areas Subsequently, the user is provided with the damaged transaction card. Thus, whenever a transaction performed with the transaction card, the damaged optical medium thereon is optically sampled for determining if the samples are consistent with the encoded mapping stored by the financial institution. If so, then the transaction may be allowed. If not, then the transaction is canceled.

In a fifth collection of embodiments of the present invention, authentication of a user requesting a financial transaction is provided. In one such embodiment, a compound that is, for instance, sensitive to touch (e.g., oil reactive, heat sensitive and/or amino acid sensitive) may be layered or coated on an optical medium included on a transaction card (e.g., credit card). Thus, assuming the touch sensitive compound (e.g., a polymer) is sufficiently sensitive so that a user's fingerprint is reliably and accurately duplicated on the compound thereby causing a change in the optical characteristics of the optical medium, then once a fingerprint is provided on the touch sensitive compound, it can be optically sampled for sensing

10

15

20

25

30

35

Next, in step 2216, a process is Internet computer). activated on the user's Internet access device for optically sampling the predetermined touch sensitive area of the optical disk. Then, in step 2220, an encoding of the samples is transmitted to the particular Internet node responsible for determining the authenticity of the transaction. Thus, in step 2224, this particular Internet node compares the samples with a previously stored representation of the user's fingerprint for determining whether the samples are consistent with the fingerprint Accordingly, if the samples representation. sufficiently consistent, then the transaction is completed as in step 2228. Alternatively, if this is not the case, then the transaction is voided as in step 2232.

In the sixth collection of embodiments of the present invention, information related to an item can be encoded on a time sensitive optical medium that changes optical characteristics over that the information time so transforms from readable to unreadable, or from unreadable In particular, certain compounds such as are to readable. disclosed above relating to the first collection of embodiments of the present invention may be utilized in the present collection of embodiments. For example, certain time sensitive items may require corresponding data for labeling, identifying and/or documenting of the items. instance, such items may be cashier's checks or money orders that must be used in a financial transaction in a predetermined time period. That is, by using the present invention, bank routing numbers or other fields may be provided on a time sensitive polymer that becomes unreadable after a predetermined time has expired. prior to becoming unreadable, such identification data may be read by an automatic or computerized check clearing system, whereas after a predetermined time of, e.g., light exposure and/or oxygen exposure, the data becomes

10

unreadable. Additionally, event tickets and/or time sensitive medical supplies may also be similarly labeled with polymers of the present invention.

Accordingly, the present invention has been described at some degree of particularity directed to the exemplary embodiments of the present invention. It should be appreciated, though, that the present invention is defined by the following claims construed in light of the prior art so that modifications or changes may be made to the exemplary embodiments of the present invention without departing from the inventive concepts contained herein.

10

15

20

25

35

## What is claimed is:

- 1. A method of limiting access to data stored on an optical medium, comprising the steps of:
- (a) rotating an optical disk in a disk drive at a selected rotational speed, said optical disk including a substrate encoded with information stored thereon as a plurality of readable data structures and including a reactive compound contacted by a light for reading the data structures, said reactive compound operative in an ambient environment containing oxygen to change optical transmission in response to irradiation by said light for an accumulated duration of time, wherein said light has a beam wavelength within a selected range; and
- (b) directing an interrogating beam of the light having a beam wavelength that is within said selected range toward said substrate layer and through said reactive compound for the accumulated duration of time.
- 2. The method of limiting access to data according to Claim 1 wherein said interrogating beam is directed at said substrate for a continuous interval of time that is sufficient to cause said change in optical transmission.
- 3. The method of limiting access to data according to Claim 1 wherein said interrogating beam is directed at said substrate for a plurality of discrete intervals of time sufficient to cause said change in optical transmission.
- 4. The method of limiting access to data according to Claim 1 wherein said beam wavelength is in a range of 780 to 820 nanometers (nm).
- 5. The method limiting access to data according to Claim 1 wherein said beam wavelength is approximately 650 nanometers (nm).
  - 6. The method of limiting access to data according to Claim 1 wherein said step of directing said interrogating beam at said substrate layer is accomplished

15

20

25

by selectively advancing said interrogating beam radially across an outermost surface of said optical disk until said interrogating beam interacts with said reactive compound for a plurality of discrete intervals of time sufficient to cause said change optical transmission.

- 7. A method of limiting access to data according to Claim 1 wherein said beam intensity is approximately .5 to 1.0 milliwatts (mW) of power.
- 8. A method of limiting access to data according to Claim 1 wherein said beam wavelength is approximately 780 nanometers (nm).
  - 9. An optical disk adapted for use in an optical readout system of a computer that includes a light source operative to produce an interrogating beam of light for reading data structures, comprising: (a) reflective layer encoded with information stored thereon as a plurality of data structures that are readable by an interrogating beam of light;
  - (b) a substrate disposed in a confronting relationship with said reflective layer;
    - (c) a film of a reactive compound superimposed over at least some of said data structures, said reactive compound selected to be of a type which is operative to change physical characteristics in response to a selected stimulus, thereby to affect readability of the data by said interrogating beam of light.
    - 10. An optical disk according to Claim 9 wherein said reactive compound is interposed between said reflective layer and said substrate.
- 11. An optical disk according to Claim 9 wherein said reflective layer is contoured to include a sequence of pits and lands which define said plurality of data structures, said reactive compound superimposed over at least some of said pits and lands.

20

- 12. An optical disk according to Claim 9 wherein said reactive compound is supported on an outer surface of said substrate and has a thickness in a range of approximately 0.14 to 0.6 microns.
- 13. An optical disk according to Claim 9 wherein said stimulus is selected from a group consisting of visible light, infrared light, an ambient environment containing light and air.
- 14. An optical disk according to Claim 9 wherein said stimulus is light and wherein said reactive compound is a photoreactive material.
  - 15. An optical disk according to Claim 9 wherein said reactive compound comprises selected from a spiropyran class of photochromic compounds.
  - 16. An optical disk according to Claim 15 wherein said reactive compound comprises 6-nitro-1'3'3'-trimethylspiro[2H-1-benzothiopyran-2,2'-indoline].
  - 17. An optical disk according to Claim 9 wherein said reactive compound is operative to change to an optically darkened state in response to an interrogating beam wavelength of approximately 780 nanometers (nm) and thereafter return to an optically clear state in response to irradiation by a beam of light having a wavelength of approximately 337 nanometers (nm).
- 25 18. An optical disk according to Claim 9 wherein said stimulus is an ambient environment containing light and oxygen and wherein said reactive compound has the chemical formula:

20

25

5 H C C C CH3

## COMPOUND 1

19. An optical disk according to Claim 9 wherein said stimulus is an ambient environment containing light and air and wherein said reactive compound has the chemical formula:

- 20. An optical disk according to Claim 9 wherein said stimulus is air and wherein said reactive compound is operative for an accumulated duration of time to oxidize and alter an optical characteristic of the compound.
  - 21. An optical disk according to Claim 9 wherein said reactive compound is operative to change from an optically transparent to an optically opaque condition wherein said reactive compounds absorbs light having a wavelength within a selected range.
  - 22. An optical disk according to Claim 21 wherein said wavelength is approximately 780 nanometers (nm).
- 30 23. An optical disk according to Claim 21 wherein said wavelength is approximately 650 nanometers (nm).

## SUBSTITUTE SHEET (RULE 20)

10

15

20

25

30

35

58

- 24. An optical disk according to Claim 9 wherein said reactive compound is a chemically reduced form of a dye.
- 25. An optical disk according to Claim 9 wherein said reactive compound is selected from a group of dyes consisting of methylene blue, brilliant cresyl blue, basic blue 3 and toluidine blue 0.
- 26. In an optical disk for use in an optical readout system of a computer wherein said optical disk includes an inner substrate layer having a substrate surface encoded with information stored thereon as a plurality of data structures and an outer layer and wherein said optical readout system includes a disk drive operative to rotate the optical disk at a selected rotational speed, a light source operative to produce an interrogating beam of light at a selected beam wavelength and at a selected beam intensity and to direct said interrogating beam of light at the data structures, and a detector operative to collect a returned component of said interrogating beam and to output signal in response thereto, an produce comprising a film of reactive compound improvement superimposed over at least some of said data structures, said reactive compound operative to change its physical characteristics in response to a selected environmental stimulus thereby to affect readability of the data by the interrogating beam of light.
- 27. The improvement of Claim 26 wherein said reactive compound is responsive to irradiation by the interrogating beam for an accumulated duration of time to change physical characteristics thereby to mask said data structures and to render said data structures undetectable by the optical readout system.
- 28. An article of manufacture adapted to be encoded with data and further adapted so that duplication of the data by an optical scanning machine may be inhibited, comprising:

## SUBSTITUTE SHEET (RULE 28)

10

15

20

25

- (a) a substrate fabricated from a selected material and having a substrate surface which contains the data; and
- (b) a reactive compound coating at least a portion of said substrate surface, said reactive compound operative to change from an optically transparent state to an optically opaque state in response to irradiation for an accumulated duration of time by infrared light having desired characteristics thereby to prevent light from the optical scanning machine from penetrating said reactive compound and to render the data undetectable by the optical scanning machine.
- 29. A method of limiting the use of information stored with an optical medium, comprising:

providing, to an optical reader, the optical medium having information for performing a desired action;

determining whether an expected profile of a purposefully induced change in the access of the information is detected;

performing the desired action using the information when said expected profile is detected; and

prohibiting said step of performing when said expected profile is not detected.

- 30. A method as claimed in Claim 29, wherein said optical medium is one of a compact disk and a digital versatile disk.
- 31. A method as claimed in Claim 29, wherein said step of determining includes detecting said purposefully induced change as one of: a distinctive pattern of errors, and a distinctive pattern of an absence of errors.
- 32. A method as claimed in Claim 31, wherein said step of detecting includes detecting one of the distinctive patterns by determining a related to one of the errors and the absence of errors.
- 33. A method as claimed in Claim 29, wherein said 35 step of determining includes:

10

15

20

25

sampling locations on the optical medium for detecting data access errors, wherein location data related to the detection of the data access errors is obtained;

comparing the expected profile with the location data for detecting said change in the access of the information.

- 34. A method as claimed in Claim 33, wherein said step of comparing includes evaluating a function dependent on one of: a number of errors detected, a relative number of errors detected, a pattern of errors, a density of errors detected and a location of errors detected.
- 35. A method as claimed in Claim 34, wherein a result of said function indicates that said expected profile is detected when there is at least one of: a minimum threshold number of errors detected, and a minimum threshold density in the number of errors detected.
- 36. A method as claimed in Claim 34, wherein a result of said function indicates that said expected profile is detected when there is at least one of: a maximum threshold number of errors detected, and a maximum threshold density in the number of errors is detected.
- 37. A method as claimed in Claim 33, wherein said step of sampling includes detecting data access errors not capable of being corrected by error correction modules receiving data via the optical reader.
- 38. A method as claimed in Claim 29, further including a step of damaging the optical medium by one of: a chemical reaction and a mechanical activity;

wherein said step of damaging is for obtaining said expected profile.

- 39. A method as claimed in Claim 38, wherein said step of damaging by a mechanical activity includes changing a reflective characteristic of the optical medium by one of: tearing and etching a layer of the optical medium.
- 40. A method as claimed in Claim 39, further including a step of encoding one of a damaged and undamaged

15

20

25

30

portion of the optical medium for identifying a financial transaction card having said optical medium, after said step of damaging is performed.

41. A method as claimed in Claim 29, wherein said step of performing includes correcting data access errors detected as part of said expected profile;

wherein said step of correcting is performed during said performing of the desired action.

- 42. A method as claimed in Claim 41, wherein at least some of said access errors are induced by microdots.
  - 43. A method as claimed in Claim 42, wherein said microdots each have a size of approximately less than 1000 microns.
  - 44. A method as claimed in Claim 29, further including a step of creating access errors as an instance of said expected profile prior to performing said step of providing.
  - 45. A method as claimed in Claim 44, wherein said step of creating includes incorporating into the optical medium, a means for authenticating the optical medium, wherein the information on said optical medium includes one of an audio presentation and a multimedia presentation.
  - 46. A method as claimed in Claim 38, wherein said step of damaging the optical medium includes changing a reflective characteristic of the optical medium by one of: exposing the optical medium to a reactive chemical, rupturing a chemical container attached to the optical medium, and exposing a predetermined part of the optical medium having a light sensitivity to an effective amount of light for changing the reflective characteristics of the optical medium.
  - 47. A method as claimed in Claim 38, wherein said step of damaging includes removing an item attached to the optical medium.

10

15

20

25

- 48. A method as claimed in Claim 29, further including a step of reducing access errors for obtaining said expected profile.
- 49. A method as claimed in Claim 48, wherein said step of reducing includes performing one of: a chemical reaction and a mechanical activity for changing a reflective characteristic of the optical medium.
- 50. A method as claimed in Claim 49, wherein said step of performing includes removing an attached layer from the optical medium.
- 51. A method as claimed in Claim 49, wherein said step of performing includes changing a reflective characteristic of the optical medium by one of: purposefully exposing the optical medium to a chemical rupturing a chemical container of the optical medium, and exposing a predetermined part of the optical medium having a light sensitivity to an effective amount of light for reducing the access errors.
- 52. A method as claimed in Claim 29, wherein said step of performing includes conducting a financial transaction, wherein said optical medium is included on a card for conducting the financial transaction.
- 53. A method as claimed in Claim 52, wherein said step of determining includes reading identifying data on said card for identifying a previously stored representation of said expected profile.
- 54. A method as claimed in Claim 29, wherein the information includes one of: graphical data, video data, audio data, text data and a software program.
- 30 55. A method as claimed in Claim 29, wherein said step of determining includes attempting to access a portion of the information residing within a predetermined part of the optical medium where the expected profile resides, wherein the predetermined part includes a minority of a total storage capacity of the optical medium.

30

- 56. A method as claimed in Claim 29, further including a step of deactivating an error correction module.
- 57. A method as claimed in Claim 56, wherein said step of deactivating is performed prior to each performance of said step of determining.
  - 58. A method as claimed in Claim 57, further including a step of reactivating the error correction module after said step of determining.
- 59. A method as claimed in Claim 29 further including steps of:

encoding said purposefully induced change; and outputting said encoded change to a user of the optical medium waiting to perform the desired action.

- step of encoding includes encrypting said purposefully induced change together with identification data related to at least one of: an identity of the user, and an identity of at least one component of a device used for processing the information on the optical medium.
  - 61. A method as claimed in Claim 60, wherein said step of encrypting includes determining an identifying code for one of a central processing unit and a peripheral processing unit as said at least one component.
  - 62. A method as claimed in Claim 29, wherein said step of providing includes purposefully inducing a change in access errors at each of one or more locations of the optical medium for instantiating said expected profile.
  - 63. A method as claimed in Claim 62, wherein said step of purposefully inducing includes:

removing the optical medium from the optical reader; altering an optical characteristic of the optical medium; and

providing, again, said optical medium to the optical reader.

15

20

25

35

64

- 64. A method as claimed in Claim 62, wherein said step of purposefully inducing includes changing one of an optical reflectance and an optical transmittance.
- 65. A method as claimed in Claim 62, wherein said step of purposefully inducing includes one of rendering unreadable an initially readable portion of the optical medium and rendering readable an initially unreadable portion of said optical medium.
- 66. A method as claimed in Claim 62, wherein said step of purposefully inducing includes providing an image of a body part on a touch sensitive portion of said optical medium.
  - 67. A method as claimed in Claim 66, further including a step of comparing a representation of said provided image with a previously stored representation of a body part image for determining a consistency between said provided image representation and said previously stored image representation.
  - 68. A method as claimed in Claim 67, wherein said step of comparing includes a step of transmitting said representation of the provided image on a communications network for performing electronic commerce.
  - 69. A method as claimed in Claim 66, wherein said touch sensitive portion includes a compound reactive to one of heat, pressure, and a bodily produced substance.
  - 70. A method as claimed in Claim 29, wherein said step of determining includes identifying said optical medium using an inputted code describing the expected profile.
- 30 71. A method as claimed in Claim 70, wherein said inputted code was previously provided to a user desiring to perform the desired action.
  - 72. A method as claimed in Claim 70, wherein said inputted code was output during a previous performance of said step of determining.

10

30

73. A method of limiting the use of information stored on an optical medium, comprising:

providing, to an optical reader, an optical medium having information for performing a desired action;

detecting an expected profile of a change in access errors for the information on the optical medium;

comparing an encoding of the change with a user input; performing the desired action using the information when said encoding provides a favorable comparison with the user input; and

prohibiting a performing of the desired action when said encoding provides an unfavorable comparison with the user input.

74. A method as claimed in Claim 73, further including a step of encrypting together a representation of said change and identification data related to at least one of: an identity of the user, and an identity of a device for accessing the information on the optical medium;

wherein a result of said step of encrypting yields 20 said encoding.

- 75. A method as claimed in Claim 74, wherein said step of detecting includes determining said change in the access errors by mapping locations of the access errors in at least one predetermined portion of the optical medium.
- 76. A method as claimed in Claim 75, wherein said predetermined portion extends to only a minority of the total data storage capacity of the optical medium.
  - 77. A method as claimed in Claim 73, wherein said step of determining includes using a representation of locations of the access errors in an encryption process for obtaining said encoding.
    - 78. A method as claimed in Claim 73, wherein data of said user input was obtained by the user from a previous attempt to access the information on the optical medium.

10

15

20

25

30

79. An apparatus for limiting the use of information stored with an optical medium, comprising:

an optical medium having stored information, wherein said information is used in performing a desired action;

means for producing a change in the access errors encountered when accessing data locations for information on the optical medium, wherein the change corresponds with an expected profile;

means for detecting whether an instance of the expected profile has occurred;

means for determining when to perform the desired action using an output from said means for determining whether said instance has occurred.

- 80. An apparatus as claimed in Claim 79, further including means for performing the desired action when the instance of the expected profile is detected.
- 81. An apparatus as claimed in Claim 79, wherein said means for performing includes one of: means for loading software onto a computer, means for presenting a presentation, and means for conducting a financial transaction.
- 82. An apparatus as claimed in Claim 79, further including:

means for prohibiting an activation of the desired action when an instance of the expected profile is not detected.

83. An apparatus as claimed in Claim 79, further including:

means for performing the desired action until an instance of the expected profile is detected.

84. An apparatus as claimed in Claim 83, wherein said means for performing the desired action includes means for reading identification data from said optical medium, wherein said optical medium is provided on a financial

10

15

20

25

transaction medium, and said optical medium is one of: light sensitive and oxygen sensitive.

- 85. An apparatus as claimed in Claim 84, wherein identification data includes bank routing data.
- 86. An apparatus as claimed in Claim 79, wherein said optical medium includes a digitally encoded optically reflective material.
- 87. An apparatus as claimed in Claim 86, wherein said optically reflective material is included in one of a compact disk, digital versatile disk, and a financial transaction card.
- 88. An apparatus as claimed in Claim 79, wherein said desired action includes one of: loading information into a computer memory, performing an audio presentation, performing a multimedia presentation, and performing a financial transaction.
- 89. An apparatus as claimed in Claim 79, wherein said means for detecting includes means for sampling data in one or more locations of the optical medium.
- 90. An apparatus as claimed in Claim 79, wherein said means for producing is attached to said optical medium.
- 91. An apparatus as claimed in Claim 79, wherein said means for producing includes one of: a means for increasing access errors, and a means for decreasing access errors.
- 92. An apparatus as claimed in Claim 91, wherein said means for increasing access errors includes one of: a chemical sac, a ripcord, an etching means for etching a surface of the optical medium, and an embedded light reactive chemical in the optical medium.
- 93. An apparatus as claimed in Claim 91, wherein said means for decreasing data access errors includes one of: a data mask attached to the optical medium, and a chemical sac attached to the optical medium.
- 94. An apparatus as claimed in Claim 79, wherein said35 means for producing includes an instrument detached from

10

15

20

25

30

35

said optical medium, wherein said instrument changes an external surface of said optical medium when applied to the optical medium.

- 95. An apparatus as claimed in Claim 94, wherein said instrument includes one of: means for scoring, and means for removing a layer of said optical medium.
- 96. An apparatus as claimed in Claim 79, further including an encoding means for encoding a representation of the change in the access errors, wherein said means for encoding includes means for outputting to a user encrypted data including an encryption of a combination of: (a) the change in the access errors, and (b) at least one of: an identification of the user and an identification a device for accessing the information on the optical medium.
- 97. An apparatus as claimed in Claim 96, wherein said means for outputting instructs a user to copy said encrypted data.
- 98. An apparatus as claimed in Claim 79, wherein a user desiring access to the information activates said means for producing prior to gaining access to the information.
- 99. An apparatus as claimed in Claim 79, further including storage for storing a representation of the change in the access errors, wherein said representation is referenced in said storage using an identification of a user having the optical medium.
- 100. An apparatus as claimed in Claim 99, wherein said representation is used in a verification process of a financial transaction.
- 101. A method of limiting access to stored data on an optical medium, comprising:

inserting the optical medium into an optical medium access device for accessing information in at least one of a predetermined first storage portion and a predetermined second storage portion of the optical medium;

10

15

25

35

activating a desired computer application, wherein to perform said application, information in said predetermined second storage portion must be used;

purposefully inducing a change in the first storage portion, wherein said change is irreversible;

obtaining a response indicative of whether the purposefully induced change exists; and

determining whether to use the information in said predetermined second storage by accessing said response indicating the existence of said change.

- 102. A method as claimed in Claim 101, wherein said step of purposefully inducing includes damaging an optical characteristic of the first storage portion.
- 103. A method as claimed in Claim 101, wherein said step of purposefully inducing includes one of: removing a layer from the first portion, causing a layer of the first portion to become opaque, marring a layer of the first portion, and chemically distorting an optical characteristic of the first portion.
- 20 104. A storage medium having limited access, comprising:
  - a first storage portion of the storage medium, wherein said first storage portion includes one or more data storage locations, wherein the locations are related to a data accessibility profile;
  - a means for changing the accessibility of data at the locations, where the change is purposeful and substantially irreversible;

wherein when said means for changing is applied to the locations, said profile is obtained.

- 105. A storage medium as claimed in Claim 104, wherein said storage medium is an optical disk.
- 106. A storage medium as claimed in Claim 104, wherein said means for changing includes a detachable portion of the storage medium, wherein the data accessibility profile

10

15

20

25

30

is detected during an access of the locations when said detachable portion is detached from the storage medium.

- 107. A storage medium as claimed in Claim 104, wherein said means for changing generates one of a decrease and an increase in the number of errors during access to the data at the locations.
- 108. A storage medium as claimed in Claim 104, wherein data in a second storage portion of the storage medium is accessible in response to an indication that said data accessibility profile exists.
- 109. A method of limiting access to stored data on a storage medium, comprising:

inserting the storage medium into a storage access device for accessing information in at least one of a predetermined first storage portion and a predetermined second storage portion of the storage medium;

activating a desired computer application, wherein to perform said application, information in said predetermined second storage portion must be used;


purposefully inducing a change in the first storage portion;


selecting a sampling of a plurality of the storage medium locations, wherein the locations of the sampling are selected so that there is a predetermined density of samples within the first storage portion;

detecting said change by accessing the locations of the sampling;


obtaining a response indicative of whether the purposefully induced change exists; and


determining whether to use the information in said predetermined second storage by accessing said response indicating the existence of said change.






SUBSTITUTE SHEET (RULE 26)







SUBSTITUTE SHEET (RULE 20)

4/19







**SUBSTITUTE SHEET (RULE 28)** 



09/646/4/



PCT/US97/08842






Fig. 11A





Fig. 11B

SUBSTITUTE SHEET (RULE 26)






FIG. 12





Fig. 13A



SUBSTITUTE SHEET (RULE 26)

PCT/US97/08842






Fig. 14A




Fig. 14B

## SUBSTITUTE SHEET (RULE 26)

12/19




Fig. 15A






Fig. 15B

## SUBSTITUTE SHEET (RULE 28)









Fig. 17A



SUBSTITUTE SHEET (RULE 28)





Fig. 18






Fig. 19B







Fig. 20





SUBSTITUTE SHEET (RULE 28)



(TUE) 08. 01'00 12:02/ST. 12.00/NO. 3561892125 P 7

- FROM

PTO/SB/01 (8-95)
Approved for use through 10/31/98 OMB 3651-0032

e a								
		S. Depart	ment of Commer		omey Dooket Number	369	9-2-PUS	
ev.			d Trademark Offi	First	st Numed Inventor	MC	LAUGHLIN, MGIK	
	DECLARA				COI	IPLETE IF IGNOW	N	
	UTILITY O			App	pliculium Number			
	PATENT A	PPLIC	ATION	Fat	ng Date			
	Declaration Of	R m	Declaration		oup Art Unik			
3	Submitted with Initial Filing	. 🗖	Submitted after solital Faling		priving Namo			
,	butieve i am the origino island become of the stubi	e address al, first ers ect matter	and efficienthip solo inventor (F which is dismed	only one. for which	ated below next to any name name is finited below) at an on a pretent its sought on the laws			names are
-	"COPY I	PROTEC	TABLE OPT		EDIA DEVICE AND MET	HODOLOGYT	HEREFOR"	
				(7)	(tie of the Invention)			
he :	specification of which							
	is attached hereto							
-	OR was fied on	ſ	05 June 1997	· · · · · · · · · · · · · · · · · · ·	an United States Application	Number of PCT in	nemalional	
		3			*			
X)	(MARDOMAAA)	į			]			
	Application Number Increby state that I have any amendment specific	e reviews	red above.	d the cont	and sees remended on MAROD/YYYY) bends of the above identified spi		g the chains, as as	
i he	Application Number increasy state that I have any amendment specific traduculadge the duty reby claim foreign pilor andor's certificate, or §3	re raviewa cally refer to discloss fity benefit 95(a) of a	d and understand ned above. Information white sunder Title 35, by PCT internation	d tree comb	man of the store identified spi tental to patentability as defined also Code § 119 (a)-(d) or § 36 salton which designated at least too the form and the spin of t	in Tide 37 Code of 5(b) of any loreign tone country other don for patent of ir	g the charts, as as Federal Regulation Spplicabin(s) for	one, § 1.56.
i he invi	Application Number increby state that I have any amendment specific tracknowledge the dusy meby claim foreign prior prior's certificate, or \$5 decr., skeet below and laternalione) application.	re reviews cally refer to disclose fity benefit 95(a) of se figure atso. A flavoring a	d and understand red above: a information white is under Title 35, by PCT internation identified below, a filling date below.	d tree comb	MAKODYYY)  tents of the atoms identified ap- tental to patentiability as defined alies Code § 119 (a)-(3) or § 36 salion which designated at leas- ing the box, any foreign applica- tic application on which priority	in Tide 37 Code of 5(b) of any loreign tone country other don for patent of ir	g the charts, as as Federal Regulation Spplicabin(s) for	mended by one, § 1.56. palent or fates of e, or of any
i he invi Am Pol	Application Number increasy state that I have any amendment specific traduculadge the duty reby claim foreign pilor andor's certificate, or §3	re reviews cally refer to disclose fity benefit 95(a) of se figure atso. A flavoring a	d and understand ned above. Information white sunder Title 35, by PCT internation	d tree comb	man of the store identified spi tental to patentability as defined also Code § 119 (a)-(d) or § 36 salton which designated at least too the form and the spin of t	in Title 37 Code of 5(b) of any localign one country other don for patent or ir as claimed.	g the claims, as a federal Regulation application(s) for then the Linked S wentor's certificate	mended by one, § 1.56. palent or lates of e, or of any
i ne invi Apo	Application Number in terraby state that I have any amendment specific tradvowledge the duty reby claim foreign prior man's centificate, or \$3 order, kitted below and international pagication have foreign Application have foreign Application.	re reviews cally refer to disclose fity benefit 95(a) of se figure atso. A flavoring a	d and understand red above: a information white is under Title 35, by PCT internation identified below, a filling date below.	d tree comb	MMMODYYY)  tents of the above identified ap- tental to patentability as defined  ales Code § 119 (a)-(d) or § 36- ation which designated at less ing the box, any toneign applica- ting the pox, any toneign applica- tion and find priority  Foreign Filing Dute	in Tide 37 Cade of 5(b) of any foreign cone country other don for patent or ir as claimed.	g the charms, as as Federal Regulation application(s) for then the Linked S wenter's certificate Contined Cop	one, § 1.56. palent or letes of e, or of any
i ne invi	Application Number inemby state that I has any amendment specific tracknowledge the duty steby claim foreign prior order is certificate, or \$5 indica, licited below and laternational application hiumbar(s).	re reviews cally release to disclose the benefit (SSQs) of an indee about the many a	d and understandered above.  o information white sunder Title 35, by PCT information distributed below, tilling data below.  Country  Lambers are listed uniformation and the sundered below, tilling data below.	of the comb ich is mail United Si und applic by checking a that of the	MMMODYYYY)  sents of the attorne identified apa- terral to patentability as defined  ales: Code § 119 (a)-(d) or § 36- attorn which designated at less ing the box, any tonega epola- terral processor and the priority  Foreign Filing Dute (NAM/DDYYYY)	in Title 37 Code of 5(th) of any foreign cone country other son for patent of the schimed.  Prostly Not Clemed.	g the chires, as as Federal Regulation specialistics for the trained 3 wenter's continues Continued Cop Vos	one, § 1.56. patent or tales of e, or of any y Attached?
i ne invi	Application Number inemby state that I has any amendment specific tracknowledge the duty steby claim foreign prior order is certificate, or \$5 indica, licited below and laternational application hiumbar(s).	re reviews cally release to disclose the benefit (SSQs) of an indee about the many a	d and understandered above.  o information white sunder Title 35, by PCT information distributed below, tilling data below.  Country  Lambers are listed uniformation and the sundered below, tilling data below.	of the comb ich is mail United Si und applic by checking a that of the	MMMODYYYY)  tents of the atoms identified aparents of the atoms identified aparents of the atoms identified as a defined atoms which designated at leasting the box, any toneign application on which priority  Foreign Filing Date (NAMODYYYY)	in Title 37 Code of 5(th) of any foreign cone country other son for patent of the schimed.  Prostly Not Clemed.	g the chires, as as Federal Regulation specialistics for the trained 3 wenter's continues Continued Cop Vos	one, § 1.56. patent or tales of e, or of any y Attached?
i ne invi	Application Number inemby state that I has any amendment specific tracknowledge the duty steby claim foreign prior order is certificate, or \$5 indica, licited below and laternational application hiumbar(s).	re reviewe cally release to disclose fly benefit psca of se redease of hereng a	d and understandered above.  o information white sunder Title 35, by PCT information distributed below, tilling data below.  Country  Lambers are listed uniformation and the sundered below, tilling data below.	of the conhich is mail lich is mail limited Ski limited Ski by checkli by checkli control of the checkli by checkli control of the checkli	MMMODYYYY)  sents of the attorne identified apa- terral to patentability as defined  ales: Code § 119 (a)-(d) or § 36- attorn which designated at less ing the box, any tonega epola- terral processor and the priority  Foreign Filing Dute (NAM/DDYYYY)	in Title 37 Code of 5(th) of any foreign cone country other son for patent of the schimed.  Prostly Not Clemed.	g the chires, as as Federal Regulation specialistics for the trained 3 wenter's continues Continued Cop Vos	mended by one, § 1.56. palent or laiss of e, or of any y Attached? No

Borden Veter Statement: (Ne form as extramed to the c. A hours as compared. Three sit way depositing upon the needed or the summer case and provided cases. Published Techniques (D. C. Section of Leonard Statement (D. C. Section of Leonard Leo

			DECL	AR	ATIO	ON			1		-	_			Pa	ge 2				
application	ın daz	the be	melit under ig the Unite rior United stedge the	Table of Si	35, Uni	led Star	, Salad be	NOW BIS	d, in	MOORT II	s the	SUR	Mact ma	iler :	of each	of the	CENT	BOITH The 25	i selent 4	ion es Shehea
	Pers		deadon	-		PCT	Parent mber				Par	ent i	Filing D XXVVX	ate:					nt Numb	
As a nam	ed to	vendo	PCT Inten , I hereby a ok Office of	ppoi	nt the fo	lowing												lect ay I	business	in the
LEL .	m Na OR		and/or ag				AN RC					_	;	ineste Cuerri	oner or	- label				
	2 410		yana y				Registra	<b>Mon</b>	T			,	Mar	ne					Registrati Numbe	
ZINGER,	ITAL					-	29.12		+	STAVE	SHL S	ARI	RINA CI	ROY	<b>NEY</b>				33,374	
GROSE			F:			- 1	31,71		- 1	HANSE	en, L	EW	SO.					[	35,536	i
TOMPKI						1	30,98		1	KOVA	ш, .	<b>203</b>	SHE						33,005	i
BLAKEL						1	31,32						GLAS V	¥.				1	37,739	ı
CONNEL			•			Ì	32.02	<u>M</u>	- [	KUGL	R. E	RU	CE A.					1	38,942	:
CROOK		-	.M.			Į	31,07	M	1	BRUN	œ۷,	RO	8 <b>9</b> 0 F	t.					39,617	<u> </u>
			ey(a) and/o	205	entis) ca	med on	3 800055		5/19	et altac	hed	hère	eto-							
<del></del>			espandona			Custon Number label	10/							O	٠ (	3		55 belo	randence W	
Name			JOSEPH I	E. KO	WASIK															
Address					DWAY,		1200													
Address					<u>`</u>						_									
City		ENVE	R						_		510	e	O	OLO	RADO				0202-514	<b>17</b>
Country	U	WIED	STATES C	FA	MERICA			ephone		(303)						Fex		J3) 663		
believed		true: Fac	t mi skrtem and further r brapisom validity of t	क्रमा स्टब्स	or both	, under	is were n Section 1	001 of 1	n e	15 of 1	e and ledg he U	the office office	e per etal et willing et States	fals Cor	nte ma e state ie and	de on mento that su	भारतामा इसर्व से इसे प्रति	eliton dr le like s Sul faku	nd belief : no made a e statema	are ire ints
	f Sole	or Fir	a Inventor.							Fami	_	pet	ition has	s bes	in Med	for the	s until	mod Im	Suffix	1
Given Name	Me	ń.					Ministr (Palital			Nam		M	(augist	n					eg. ar.	<u> </u>
Inventor Signatur	2 2													1	Opetic:					
Residen	DE 0	N T	Baton Rox	Ge_			State	Louis	leme	•		Œ	entry	US	A		Citiz	enship	USA	
Post Off	ice A	dife	5514	SP	oimer C	ourt		-												
Post Of																				
-		Ross		7	State	Louisk	una enu	Zip	71	0808		٦	Count	y	USA			opticant shortly	T	
				L				L	<u>.                                    </u>			1		1						

X

be a om	s sign	(+) M3M	e this box	٠ـــــ											
		Q	ECLA	RATI	DN			<u> </u>		ADO S	CLOWNT I	HIVENT Ital Shi	CIR(8) est		
terne of	7450	oral Joi	s inversor.	र्ते अस्त						A pelibor	has been	සහේ භා	this wenge	ad inven	tor
Siven Marrie	i filler	,				Middle Initial	δ.	Førsty Name	Lac	kritz.				offin g dr.	
menter Signatur	3.										Date				
Residen	e Ch	Cup	ortino		$\neg \neg$	State	Califon	NE S	Ca	mary U	SA		kzenskip	USA	
Post Off	ice Ad	decas	10952 8	amanca ()	ÚAE.										
Post Off	oc Ad	drass												<b>.</b>	
Chy C	Superi	ino		State	Californi	•	Z3p	95019		Country	USA		Applicant Authority	_	
Name of	Addi	ol, lano	ni invensor	, if arry:					C	A petito	n has beer	filed to	a this untigo		dor
Given Name	Jerry	•				RAGGIO Initial	T	Family Name	Sim	iit.				effix .g. Jr	
ineerder Signatur		<u> </u>					-				Gats				
Residen		Little	SERT			State	Color	do	Co	untry U	SA	10	ilaznohip	LIBA	
City Post Of	- 1		GENT W	. Ro-land	Ave.										
Post Of			3000									*****			
	i mieto		l	State	Colorad	io i	Zβ	60120		Country	USA		Applicant Authority		
					<del>T</del>					7.0	n han han	Sied 6	or links unedo	and ime	olor
	f Add	iona: Jo	ent Invento	г, я ему.	<u> </u>	1545		Fortily	$\tau$	Tu hame	2. 140 000		F	Suffer	
Given Name	Jan	168				[mial		Name	w	aktori		γ	!	e.g .#.	1
mvento Signati	rs re	<u>`</u>	X4	<u>) (</u>	(	Q	بر				0ate 8/260				
Regide	nce Ci	灯	oulder			Same	Color	ado	a	anestry (	JSW	0	ibizeraskip	USA	
Post O	fice A	oden	5024 6	Boulder	Road										
Post O	Sice A	dáresz					,						Applicant	T	
G <sub>e</sub>	Bould	#1		State	Colora	fo	ZP	80303		Сочтту	USA		Authority	<u> </u>	
Name	of Add	Honal J	an Invent	х, ў заус	T				1	]A post	on has bee	n Sled 1	for this wasi		mior
Given Name	1,1	nadior d	2/			Mickel Indiai		Factority Names		eny				Suffix e.g. Jr.	
Irvent Signati	o/'s	4	Bra	S	pre		W	Ven	y		Date	8	· /	200	00
Reside	ince C	J/	vinapolis			State	Mary	tand V	10	country	USA		ilizenship	USA	
Post 0	Mice /	ades	63 Ge	nary Count											
Post C	Hice /	ddraza								,			L a commercial		
City	Anne	polis		State	Masyfa	PRI	Zh	21403		Country	USA		Applicant Authority		
Da.	Firel	et amili	ons and/o	(figniser	invento	n ac in	dicated	on anodice o	ntina	ation shot	1				
English B	-	0/101 4	national time	sherr)(da	y 1998X	form do	officered	by Sheridan	Ross	P.C -your	)		See Notes	to the re	quest f

1300 C

TUE: 98. 011 E0 1/2 C2/ST 12 CD/NC 0551892125 F 7

Approved for use through 10/31/96 OMB 0651-0032 Type a plus sign (+) Incide this box -- . Palent and Trademark Officer U.S. DEPARTMENT OF COMMERCE 3999-2-PUS DOMPTO U.S. Department of Commerce Attorney Docket Number Rev 6/95 Patent and Trademark Office MCLAUGHUN, MEZH First Named Inventor DECLARATION FOR COMPLETE IF KNOWN UTILITY OR DESIGN Application Number PATENT APPLICATION Faing Date Group Art Unit Declaration Declaration Submitted with Supmitted after Initta Filing Initial Filing Exampler Name As below named inventor, hereby declare that: My residence, post office address, and oftenship are as stated below rext to try name I believe I am the original, first and sole inventor (If only one name is listed below) of an original. Stat and joint Inventor (If plural trames are itsed below) of the subject matter which is delimed for which a patent is sought on the invention onlined. "COPY PROTECTABLE OFTICAL MEDIA DEVICE AND METHODOLOGY THEREFOR" (Title of the invention) the specification of which is sitsched hereto 05 June 1997 as United States Application Number of PCT International was fied on (MANDO/YYYY) (if applicable) Application Number PCT/US97/08842 മർക് യമ്മ സ്ഥാന് വർ വ (NEWOONYYYY) I hereby state that I have reviewed and understand the continue of the above Identified specification. Including the claims, as amended by any americanent specifically referred above. I adminished on the duty to disclose information which is material to obtain bottly as defined in 1 the 37 Code of Federal Regulations § 1.56 I hereby craftin foreign priority benefits under Title 35, United States Code § 118 (a)-(d) or § 365(b) of any foreign application(s) for patent or inventor's certificate or \$385(a) of any PCT international application which designates at least one country other than the United States of America, listed below and have also identified below, by checking the box, any foreign application for patent or inventor's chrifficare, or of any Pot international application having a filling date before that of the application on which bromly is claimed. Foreign Fliing Date Cartifled Copy Attached? Prior Foreign Application Country Prionty (MIMODAYYY) Not Claimed Number(s) Yes No Additional foreign application numbers are listed on a subplemental priority sheet attached hereto. thereby claim the benefit under Title 35. United States Code § 119(a) of any United States provisional application(a) listed below

Bursen Hour Statement. This farm is estimated to take 4 hours to complete. This will vary depending upon the needs of the individual case. Any comments on the kindum you are organized to complete this form should be sent to the Chief information officer. Patent and Trademain Office. Westington, OC 20231 DO NOT SEND FEES ON COMPLETED FORMS TO THIS ADDRESS. SEND TO Assistant Commissioner for Patents Washington, OC 20231

Filing Date (MM/DD/YYY)

Acorbonal provisional application numbers are listed on a supplemental profity shee! attached hereto

March 14, 1997

Application Mumber(s)

60/040,724

Type a plus sign (+) inside this box . ADDITIONAL INVENTOR(8) DECLARATION Supplemental Sheet Name of Additional Joint Inventor, if any, A cetition has been filed for this unsigned inventor Middie Family Higry Lackritz. Initial Norma Nome **e.**g. Jr. Date inventor's Signature. 8/10/00 Residence City Cupertino State California Country USA Ciazenship U\$A Post Office Address 10952 Barranca Onve Post Office Address Applicant 95019 Cupertino State Callfornia Ζþ Country 115A City Authority hisrae of Additional Joint Inventor, if any A petition has been filed for this unarghed inventor Given Middle Family Suffix Name initial Name Jerry Date Inversion's Signature Calarado Ciazenship USA Country USA Residence Littleton Stale Cib 5690 W. Rowland Ave Pour Office Address Post Office Address Country Applicant Littleton Colorado Z)p 80120 USA Authority Name of Additional Joint Inventor, if eny. A potition has been filed for this emalgned inventor Suffee Giver Middle Parity Weldon Name Initial Name # 7 11 Date inventors Signature Colorado Country USA Citizenship USA Residence City Post Office Address 6424 S. Boukser Road Post Office Address 80303 Applicant City State Colorado Ζiρ COURTRY USA Authority Name of Additional Joint Inventor, if any A peddon has been fled for this unsigned inventor Given Middle Family Sume Name J Brantoro iridəi eg Ji. Date Inventor's Elgnature Maryland Country Citizenship USA State USA Residence City Annapolis Post Office Address 63 Genay Court Post Office Address Apolicant 21403 Country USA City Annapodis State Maryland Zip Authority [X] Further applicants and/or (further) inventors are indicated on another continuation sneer Form PCT/RO/101 (continuation recor)(July 1998)(form cuplicated by Sheridan Ross P.C.-jman) See Notes to the request form

Approved for use through 10/31/96 ONB 0851-0032

FROM

PTO/SB/01 (6-95)

e a p	oka eign (+) Incide ibus I	30K [	]		Patent and Trademark	Office: U.S. DE	PARIMENI UF	CHIMIERCE
O/P1	ro us	. Depart	ment of Commerce		ney Docket Number	3999	2-PUS	
e+. 6		alent ant	Trademark Office	First	Named Inventor	MCL	aughun, Mark	
	DECLARA	TION	FOR		COMPLI	ETE IF KNOWN		
	UTILITY OF			App	isation Number			
	PATENT AP	PLIC	ATION	Falin	g Claire			
_	Declaration OR	p	Declaration	Gre	o Ari Unit			
3	Submitted with Initial Filing	لبا	Submitted after Initial Filing	Exa	murer Name			
94		acidress.	and citizenship 20		ad below next to my name tame is itsiad below) or an ongina a patent to sought on the invention	i, Gret and ;cint in n entited:	wentor (II plural ri	izmės arė
					DIA DEVICE AND METHO		EREFOR"	
L	-		-	(75	ite of the invention)			
	is abgoined hereto  OR  was filed on  (MM/DD/YYYY)	Ţ	05 June 1997		as United States Application Nu	mber or PCT Inc	<b>e</b> mational	
	Application Number	PCT	/US97/38842		rd was emended on MAPDOYYYY)		()f a	opi(cable)
l l hei invo	acknowledge the duty to reply claim foreign proofs intor's certificate, or §38	ally reter o elector y benefit 5(a) of a	e information which is under Title 35, U ny PCT information	ie mah nated State of Spring	ents of the above identified specifical to detentiability as defined in later Code § 118 (a)-(d) or § 365(b) after which designated at least or ng the box, any foreign application as which profity is	Title 37 Code of of any foreign se country other n for patent or in	Federal Regulation polication (s) for the Links S	one, § 1.56. patent or tales of
Pd	international application	UEALLE I	Country	mak on a	re application on which provity is	Priority	Carlified Cop	
P	nor Foreign Application Number(s)		Corsina		(MANA/DD/**YY)	Not Claimed	Yes	No
	Additional foreign 200	ication n	umbers are listed (	on a sup	plemental priority sheet adached	hereto.		
1 h	ereby claim the benefit (	ander Tid	e 35, United States		119(e) of any United States prov	reional application	orde) name oardw	<b></b>
	Application Nu	mber(s)			g Date (MM/DD/YYY)		Additional pro	wickent
60	/040,724		Merc	n 14, 19	<del>19</del> 7		application nu gre listed on a supplemental sheet attache	mbens s pnority
						1	but esta Anu me	nease on the

Burden Hour Statement: This form is estimated to take 4 hours to complete. This form should east any comment of time you are required to complete this form should be sent to the Chief Information officer, Patient and Trademark Office, Washington, DC 20231 DO NOT SEND FEES OR COMPLETED FORMS TO THIS ADDRESS. SEND TO Adeletant Commissioner for Palanta Washington, DC 20231

Applicant Authority

USA

Country

		DECLAR	ATION					Page	2			_
aplication of disclos	e dealgealle sed in the p	nellt under Title op the United Se for United Scale dedge the duty to available behate	tes of Ame s of PCT in	rice, fisted 50 iematonal ap	iow and, i plication i	nsolar as the in the marino legist to pain	: subject m : providec neolity as	siter of each of by the liest pen defined in Title	ithe clai sgraph ( 37. Co	ims of th of Tibe 3: Ge of Fea	is appacauc 5. Linked St ieral Regul	ate ate
U.S. I	Perent Appl Number	lcation .	þ	CT Parent Number			en filing ( IN/DD/YY		P(		ent Numbe Nicebie)	,
s a nam	ed 'nvanter	PCT Internation I hereby appoint to Office contect	it the follow	ing attorney(s							busineas ir	7 ()
Fin	m Name OR		SHE	RIDAN RO	SS P.C			Customer Number or is	ibe!			_
Lis	ł ettorney(s	sad/or ageni(s	name and	registration n	umber be	kow:						
	ŧ	vane:		Registral Number			Na	кте			Registratio Number	
NGER,	DAVID F.			29,12	7	STAVISH.		ROWLEY			33,374	
	TH, CRAIG			31,71	1	HANSEN,	-				35,536 33,005	
	ns, Micha			30,36 31,32		KOVARIK, SWARTZ,					37,739	
	Y, TODD 9.			32,02	- 1	KINGLER.					38,942	
	l Gary j Wannell	М		31,07	å	BRUNELL	ROSERT	R.			39,617	-
		y(a) and/or age	nus) name	i on a suppler	nental str	et atached	hereto					
_		espondence	Cut Nu	stomer riber or			·	OR 🗆		in correi dress be	spondence low	
ane		JOSEPH E. KO	NARIK		<u></u>	د <del>بطالی پیا</del> "	······································	.1				
Address	1	1580 BROAL		TE 1200								
€ <b>0</b> / <del>0</del> 38	+											_
Hy	DENVE	R				845		OLORADO			80202-514	
oundy	UNITED	STATES OF A	ierica		phone	(303) 863-				(333) 86		
elleved unishel	te be true: Ne hy fine o	t all statements and further that ir imprisonment, validity of the sp	these states or both, in	ments were it der Section 11	DOIDETIS	ne knowled le 16 of the L	TO THE WHITE	LITTE SE STALLSIN	TATE OF THE	T REE MICE	DO HARDE -	-
	Sale or Fit						A pelibon h	as been fied to	r this ur	signad i	nventor	
Siven Vaine	Mark			Middle Initial		Family Name	McLaugt	iller	<del></del>		Suffix e.g. Jr.	
nventor Signatur	- 1					_		Date				
P-60-	ī							3	1			

图 Additional inventors are being named on supplemental shoots) attached hereto.

Louisiana

State

Žip

70808

Post Office Address

Haton Rouge

C.
Ţ
#=: 
iges:
#
mandan.
u u

			ECLA	RAT	ON						AC	DITIONAL Suppleme	NYEN ntal Sh	TOR(S)		
ême o	f Add	idonal Jo	int Inventor,	f any:		***					A pett	on has been	filed fo	v this unsig	ned inven	tor
ven sme	Ка	rl .				Middle initial	Ř.		Family Name	Sal	neck, Jr				Buffix a.g. Jr.	
venici Igrativ			Tay	llg	lel	lu	ll		Le			Date	1	0 A	40	7
esider		ity M	illand			State	Penn	ytva tytva	nra	SO.	untry	JSA	C	tizenship	USA	
st Of	Tice A	doress	3099 Sur	rige Lak	e											
osi Of	ice A	doress.														
ily	Mikor	t .		State	Pennsylv	sing	Zip	18	337		Country	USA		Applicant Authority		
ame o	d Paid	ullonei Jo	int laverdor,	if any:	T						A petit	on has been	filed A	or this unst	greed inver	150
iver! eme	T					Middle	T		Family Name						Suffix e.g. Jr.	
ignet.			-								-	Date	-	•		-
leside Aly	nce			<del></del>		State				Co	untry		٥	itzensnip		
osi O	fice A	dd-ees														
net O	floe A	Address														
äty				320			Zip				Country	1		Applicant Authority		
lame :	of Age	îlional d	int Inventor,	H any:						[	] A pett	on has been	filed f	or this unai	gnati inva	nto
Siven Jame	T		<del></del>		<u></u>	Middle teltial	2		Family Name	T					Suffix e.g. Jr	
avent Signet												Cate				
Casicie City	FICE					State				C	ountry		0	lüzenshiç		
ost C	Mice /	Addinas														
	:Noe :	Address	<u> </u>	,	<del></del>		т	-		3				Applicant		
Post C				State			ZIp	L			Country	عصط		Authority		_
City										[	] A peli	ton has bee	n filed i	for this una	igned inve	nto T
City	of Ad	ditional J	oint Inventor	, if any:		1				····		,,			C. For	1
City	of Ad	didonal J	oint Inventor	, if any:		Middle			Family Name						Suffix e.g. Jr.	L
City Name Given Name	I or's	ditional J	oint Inventor	, if any:								Dete				
City Name Given Name Invent Signat	or's		oint Inventor	, if any:						[c	ountry	Date		Lidzen ship		
Name Given Name Invent Signat	or's une		oint Inventor	, if any:		initial				Tc	ountry	Date		Ckizenship		
City Name Given Name Invent Signat Reside	or's also	l l	sint Inventor	, if any:		initial		1		c	Ountry Country			Appilcan Authority	e.g. dr.	

P. 7

08/02/00 15:10 PAA 3004481000

natification homitact to the contract of the c

A CATA

Type a plus eign (+) Inside this box •

DECLARATION	ADDITIONAL Endor AGENT INFORMATION
	Supplemental Signal
~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~	

		Supplement	i Steet
Name	Régistration Number	Name	Plegiatration Number
HUGNES, RICHARD L. HARISRA, TELPAL S. HARTJE DANA 1.	31,254 35,172 40,536		
DALLAS PEDRETTI, ANGELA 1388, BENJAMIN B KINGPPOR, BRADLEY M. BROWN, THERESA A	42,650 42,801 44,189 32,547		
- Orichan, Burian R Duftay, Deidics J.	42,425 45,299		
			1

nang Késtit þi Þonfast ön "" - "" - "

RIONS

PTO/SB/01 (\$95)
Approved for use through 10/31/98 OMS 0651-0032

<b>YDÇ</b>	a přes sign (+) insk							
	PTO . 6/05			ment of Commence of Trademark Office			1690-3 PUS	
7					First Named Inventor		ACLAUGHLIN, MBH	
	DECLA		• • .			COMPLETE IF KNO	ww	
	ידעודע				Application Number			
	PATENT	APP	PLIC	ATION	Filing Date			
×	Declaration Submitted with	OR		Organization Submitted after	Group Art Units			(1 5 <del>- 1 - 1 - 1 - 1 - 1 - 1 - 1 - 1 - 1 - </del>
	Initial Filling			Initial Fried	Estres Name			
n ti	treffero I am the of	officer act	dross.	and efficienship are p spin inventor (if only	ss statud below near at my namo out name is fished below) or an e discholar patient to satisfic on the ke	onginal, that and jak vention antibled:	it inventor (# plums r	usmos Jne
	"COF	Y PRO	DIEC	TABLE OPTICA	L MEDIA DEVICE AND ME	THODOLOGY	THEREFOR	
L					(उद्येश की गीक (संस्थादिका)		<del></del>	
	peoficiation of white to absolved hereit GR Was lifed on (MMODITYTY)			5 June 1987	as United States Application	on Number or PCY I	<del>Nafradignal</del>	
					•••			
	Application Numbe	· [	FCTXU	S97/08 <b>9</b> 42	and were selected on		(# Ap	B <sub>f</sub> (capie)
<b>3</b> (		אפו פאבע ר	news6	ing understand the		pedfication. Includin		•
; ( ##	namby state that s my automaticant soc	יםי פעל ייעושטאנט	reinriei	ind understand the i	IMMODALLI		g the dains, es em	ended by
) ( au ) ( ) Heath Heath	nemby state that is ny amondment soe solmonifedge the di stby claim foreign p thin's certificatio, or free, Estell below as	have rem contactly to dis migraty to: \$205(2) nd have:	reture to sell	ind understand the labore.  Information which is more Trite 35. Under the property of the prop	(WANDONYYYY)  converts of the above identified a  material to potentiability as define  d Status Code & 118 (a) (d) or § 3  potentian which designated at lease coding the box.	d in Tide \$7 Code o 165(b) of any fundam su one country only sulon for palicht of l	ig the dailne, as am Federal Regulation spokeabor(e) for pr from the United St	ended by w, § 1.56, stent or stes of
Port la	nemby state that is ny amondment soe solmonifedge the di stby claim foreign p thin's certificatio, or free, Estell below as	have residently to dis stry to dis slockly ter (\$195(2)) and have:	reture to sell	ind understand the labore.  Information which is more Trite 35. Under the property of the prop	(WANDONYYY)  converts of the above literated a  material to posterizability as define  d Status Code 5 118 (a)-(d) or 5 3  posterizability which designs but at lease	d in Tide \$7 Code o 165(b) of any fundam su one country only sulon for palicht of l	ig the dailne, as am Federal Regulation spokeabor(e) for pr from the United St	ended by w, § 1.56. Stent or stens of or of any
I Hen Heren Arren Pot la	Pareby state that is ny amordinant soc solomericane the di ety claim foreign p thin's certificate, or han, topod below a memininant applica	have residently to dis stry to dis slockly ter (\$195(2)) and have:	reture to sell	ind understand the instance of above information which is more Trite 35. Linux PCT is the made in in a stance of a	(NANDONYYY)  Continues of the above identified at  material to posterizability as defined  Status Code 5 118 (at-(d) or 5 3  pricetion which chalgrained at its  coding the box, any fartist applic  of the application on which priority	d in Title 37 Code o 65(b) of any fundam as one country other asion for patent or to be as dalmed.	ig the dalms, as em i Federal Regulation application(s) for pr then the tarket \$6 wenter's confliction	ended by w, § 1.56. Hent or Mass of or of any
I nen I nen Inver	neraby state that is ny amorament ace solomoviedye the di ety claim fereign p thin's certilicato, or less, isand below a mematanah mpaka lor Fereign Applica	have residently to dis stry to dis slockly ter (\$195(2)) and have:	reture to sell	ind understand the instance of above information which is more Trite 35. Linux PCT is the made in in a stance of a	(NANOCITYYY) continues of the above literatured as material to posterizability as define d Status Code 5 118 (a)-(d) or 5 3 plication which designated at lease coding the Box, any familiar application on which priority from application on which priority From Fring Date	d in Title 37 Code o (65(b) of any fundam as one country pine asion for patent of 9 y as dalimed.	ig the dalms, as am Federal Regulation spokesbor(s) for pr men the United Statementor's conflictive Centified Copy	ended by  w, § 1.56.  Ment or  star of  or of any  Attached?
1 ( hearth model)	neraby state that is ny amoratrant ace solarowiedge the distribution, or less than a second activities to calminate a second activities and activities and a second activities and activities and a second activities and activities and activities activities activities and activities activities activities and activities	have re- softenily to dis flootly tes (1785(2)) nd have milen have	remade of refuser to the same	ind understand the instance of above.  Information which is more Trite 35. Lines PCT is remained as in the instance of a series of a serie	(NANOCITYYY) continues of the above literatured as material to posterizability as define d Status Code 5 118 (a)-(d) or 5 3 plication which designated at lease coding the Box, any familiar application on which priority from application on which priority From Fring Date	d in Trice 37 Code of 165(b) of any foreign as one counsy one colon for patent of the colon for interest.  Pricertly New Cigitized	ig the dalms, as am Federal Regulation spokesbor(s) for pr men the United Statementor's conflictive Centified Copy	ended by  w, § 1.56.  Ment or  star of  or of any  Attached?
III au	Parably state that is ny amendment ace submendedge the discharged foreign public is continued below as membering public foreign public foreign Application (Aurobortic)	trave re- perfection to the property to the pr	revise in responsibility a responsibilit	ind understand the instance and instance in the second in	(WANDONYYY)  CONTROLS OF the above literation as  Insulance to potentiability as defined  Status Code 5 118 (at-(d) or 5 3  pullation which designated at lease coding the box, any familiar appoint  of the application on which priority  Foreign Filing Data (MANDONYYYY)	d in Trise 37 Code o  RE(b) of any fundament on a country only  set claimed.  Priordy her Cigured	g the dains, as an if Federal Regulation application(c) for provinces Serventor's contilicate,  Certified Copy  Ves	ended by  w, § 1.56.  Ment or  star of  or of any  Attached?
11 num	Parably state that is ny amendment ace submendedge the discharged foreign public is continued below as membering public foreign public foreign Application (Aurobortic)	have re- critically to dis long to dis floating to \$355(2) and to the sign have	remaid a remaid and a remaid a remaid and a remaid a remaid a remaid a	ind understand the labour. Information which is information which is more Tribe 35. Under PCT standard in a subject to the labour that Country  Country  Locality  Loc	(MANOCATYYY)  contents of the above identified a  material to potentiability as define d Status Code # 118 (a)-(d) or \$ 3  primition which designated at leaseding the bon, any familiar application of the application on which priorit  Foreign Filling Date  (MANOCATYYY)	d in Trise 37 Code o  RE(b) of any fundament on a country only  set claimed.  Priordy her Cigured	g the dains, as an if Federal Regulation application(c) for provinces Serventor's contilicate,  Certified Copy  Ves	ended by  w, § 1.56.  Ment or  star of  or of any  Attached?

8: 2: 0; 11:27; Wednesday, August 02, 2000 11:37 AM

Additional Inventors are being named on supplemental sheeks) shacked hereto.

303543 7313 => MCCASKILL ; #5

James Weldon 303543 7313

(TUE) 08, 01° 00 12:03/87, 12:05/NO, 3561892125 P 8

DECI	ARATIO	N				Pa	ge 2		
t hereby claim ton branifit union application designating the Union not disclosed in the prior Union Code § 172.1 acknowledge th § 1.56 which because available	Red States of Ar of States of PCT a duly to disclos	merica, sat Internation a internati	ed beto lippe lare blue out	rund, insolar et ication in the ma h is malerial to p	s the subject lower pathid patentability	i mellion of each ad by the first p as defined in Tr	at the cist tragraph c to 37. Cor	ing of this app of Time Jis. Uni in of Federal i	eficely and St Regule
U.S. Perent Application Number		PCT Pare Number			Pacent Filin (MMDD/		Pa	roni Patent N (if applicable	
Additional U.S. or PCT intensions a nemed inventor; I tension and Trademark Office of	appoint the folio	elmu attion	era ana	lighted on a suppoi	procession	ofly sheet affaction	and to eau	i. Haci ali busin	<b>0</b> 05 m
First Name OR		RIDAN				Contempor or i	atrei [		
Liet attorney(s) and/or ag	icuria) name sur	<del></del> -		er below:	······································			Τ	-
NGER DAVIO F.		No	sirstion Hiber			larne	·	Regist Num	
ROSETH, CRAIG C.		-	,127 ,713	•		CROWLEY	1		114
DIFFRING, NICHAEL L		1 -	,500	3	. LEMB D. C. JOSEPH	E.		35,	538
LAKELY, TODO P. DINNELL, GARY J			326		DOUGLAS			37.7	
N TENNAM NOO			,020 ,071		. BRUCE A. Li, ROBERT			38.9	
Additional assomey(s) sudice	agant(8) nether			of the state of th	t hereis	- N	····	10,0	117
naen direct alt consspondenç	, Cus	itomer riber or	T			OR 🗆		corresponden se below	-00
	KOVARK		<del></del>			_ <del>l</del>		,	
dress 1500 8A	TUE , YAWIIMO	E 1200							
y DENVER				56		DLORADO	٠,٠	7	
unby UNITED STATES OF			ologina n	(303) 863	<b>8790</b>	F	Z) 8x (30)	11863 0005	
weby declare that all statemen leved to be true; and further to vidinate by fine or imprincemen y leapurates the validity of the tre of Salls or Plant inventor.	mt or both und	er Sartina	1001	Title of or a	d that off str po that with Inited State	noments made of il faise stateme s Code and that	on antonne ha and the such will	Mon and belief Nee so made ulfalse staten	ane ane ante
THE CONTRACTOR PROPERTY.				<u> </u>	h pelition its	s been Red for	gana majar	ad inventor	
		fulled Infile		Family Name	Mici_augini	in.		Suffix	T
THE MISIR							~~~	1 e.g. fr.	_i
marie Mark	1. M	7	مح			00to 916100	ì		
		72 Sinte	حرح العدة		Country	1 - 2 - 1	Citzan	phip UBA	

FROM LAW/OFFICE 3037942073 8-03-200 9:41PM ARAST 22217 AP SONTON SOUTH SOUTH CONTINUES OF SOUTH CONTRACTOR TWO TO THE CONTRACTOR Typo a plus sign (+) Inside this box . . ADDRIGHAL DEVENTURES) DECLARATION Supplemental Shart Name of Authtional Joint Inventor, if any A polition has been filed for this unagreed inventor MidSe Ferrely Sellie KLINY Name (16) Lactoite -g. *3*r STRINE California Cherophy Country USA Heridence City | Cupertino Sinte USA Pus Office Addition 1095Z Savance Drive Post Office Address Applicant Authority USA State CAPITOTIO 95010 COUNTY Capellino ΖÞ Name of Addisonal Joint Inventor, if my. A peption has been filed for this unsigned inventor **Riberiti**o Fastilly **Explicit** गपछन Name e.g. Ji 8/3/2007 LUSA Residence Littleton State Colorado USA Ciliacono hilp City Poer Other: Address 5630 W. Rowland Avc. Post Office Adds Applicant Littleton Colorado MD120 USA Ζφ Authority Name of Additional Joint Inventor, if any: A petition has been fied by the uneigned inventor Suffee NECOTE Initial Funda Name James **Name** Weston. eg. Jr 7,... invection's Date Signature **Charactly** USA Colorado . Country Residence City State Boulder Post Office Address 6424 S. Boulder Road Post Office Address Applicant 90303 USA Boulder State Cobredo ΖÞ Сэшну City Authority Name of Additional John Inventor, if any: A patition now been stat for this unsigned inventor tylick**a** Given Family Name J. Bradford. (na) METY e.g. #,

5**6**100

Maryland

💢 िंग्सीन क्षेत्रां कार्यन्त (प्रियोक्षा) संस्थित कार विकास १० २००६० ट्रांकानाक्ष्य संस्थ

Form PCE/RO/104 (communities about/Only 1998)(form deplicated by Shoridan Ress P.C. 4940)

MANY AND

21453

Country

USA

UŞA

Ottomenia.

Applicant Authority

USA

See Notes to dur request form

Signature

Residence City

Paul (Miles) Address

Post Office Address

Annessie

A:wepoils

63 Gentry Court

See Noves to the request form

()

U8/U2/UU 15:10 PAA 30344####UU Type a plus sign (+) maldo this box . [\_] ADDITIONAL WIVENTORIS) DECLARATION nores Stact A petition has been filed for this unaigned inventor Name of Additional Joint Inventor, If pay, Mode Family Marc IARRE Edwack, Jr. e.g. ↓r, Here 0310 Syrane Cidabreria State Personalization Country LIBA URA MUNIC PERSONAL CAY 3039 Swrice Lake Post Office Address Paci Office Address Accident Permyyvenia ZÞ County USA Millerd Authority Numb of Additional Joint Sevention, If only: A publican trace teach filled for this unsubgroad inventor Maddle وقاتدا Given 8 A. Jr. inithe Married Neme LOVERSED E. Signalure CHEWISTIN Suite Course CA Post Office Address Fast Office Address Country ΖÞ **CD**-Authority Name of Additional Joint Unionics, If any. A publican has been thes for this unsigned invertor Sulfe Family ca. k Napret M Date كيفيسقمن Signature Country Port Office Address Post Diffee Address Applicant Country Serie ΖÞ City Totalerni benglenu cird tot (più mead sert nobbed A Name of Additional John Inventor, if any: Suffin Middle Family 17/EZ) ₩.Jr. Dete Signaturo Citizenship Country State Residence Dray POST Officer Address Post Office Address: Applicant Zφ Country Co طحك Audiority

[ ] Further applicates and/or (further) investors are indicated on tensiles continuation share Form PCT/RD/101 (commonton about) (only 1938) (form deplicated by Standard Ross P.C.-journ)